EXHIBIT A

Bid Evaluation
Substation 6 Transformer T1

Name of Bidder: / Item Description	ABB	Waukesha Electric Systems	Howard	Delta Star	Pauwels Transformer, Inc.	WEG Transformers
Represetative:	T & D Products	Waukesha Electric	Howard	Delta Star	PowerOne, Inc.	WEG Electric Corp.
Manufacturer:	ABB	Waukesha Electric	Howard	Delta Star	CG Power	Transformer Dept.
Delivery:						
Date of Delivery In Place on Pad	28-34 Weeks	20-24 Weeks	26 Weeks	40-46 weeks	42-44 weeks	30-32 weeks
Unit Cost of Losses:						
No Load Losses Evaluated at $/kW	$ 3,990.00	$ 3,990.00	$ 3,990.00	$ 3,990.00	$ 3,990.00	$ 3,990.00
Full Load and Auxiliary Losses Evaluated at $/kW	$ 1,300.00	$ 1,300.00	$ 1,300.00	$ 1,300.00	$ 1,300.00	$ 1,300.00
Guaranteed Losses from the Proposal Form:						
No Load Losses (kW)	11.36	12.5	13.35	11.7	11.8	11
Total Losses - 55 Deg C rise (kW)	68.39	66.5	63.25	58.9	65.3	75
Auxiliary Losses (kW)	4.2	5.4	2	2	2.4	2.5
Evaluated Costs:						
Total Bid Cost	$ 594,515.00	$ 587,854.00	$ 655,000.00	$ 542,472.00	$ 464,480.00	$ 463,000.00
Adjustments to Bid Cost						
Lifecycle Cost of Losses	$ 139,693.40	$ 143,345.00	$ 138,091.50	$ 125,853.00	$ 135,092.00	$ 144,640.00
Cost of Additional Overseas Inspections						
Waranty Adjustment						
TOTAL EVALUATED COST:	$ 734,208.40	$ 731,199.00	$ 793,091.50	$ 668,325.00	$ 599,572.00	$ 607,640.00
Exception taken to any portion of the specification	None	None	None	None	None	Exception to US built