



ST. CHARLES
SINCE 1834

City of St. Charles Engineering Design and Inspection Policy Manual

**ADOPTED: OCTOBER 2009
UPDATED: FEBRUARY 2013**

ENGINEERING DESIGN AND INSPECTION POLICY MANUAL

TABLE OF CONTENTS

SECTION I. SANITARY SEWER SYSTEM

- A. DESIGN REQUIREMENTS
- B. MATERIALS

SECTION II. STORM SEWER SYSTEM

- A. DESIGN REQUIREMENTS
- B. MATERIALS

SECTION III. STORM WATER MANAGEMENT / SITE GRADING

- A. DESIGN RESTRICTIONS
- B. DESIGN REQUIREMENTS
- C. MATERIALS

SECTION IV. WATER SYSTEM

- A. DESIGN RESTRICTIONS
- B. DESIGN REQUIREMENTS
- C. MATERIALS

SECTION V. PAVEMENT / ROADWAYS

- A. DESIGN REQUIREMENTS

SECTION VI. DESIGN REFERENCES

SECTION VII. INSPECTION PROCEDURES

- A. STORM AND SANITARY
- B. WATER DISTRIBUTION SYSTEM
- C. PAVEMENT AND ROADWAYS

SECTION VIII. ENGINEERING DETAILS

SECTION I

SANITARY SEWER SYSTEM

- A. DESIGN REQUIREMENTS**
- B. MATERIALS**

A: Design Requirements:

- 1) Auger: Augering will be required at all roadway crossings unless otherwise permitted by the City of St Charles appropriate Engineering Division. Steel casing and “Cascade” spacers (or approved equal) shall be utilized. Following completion of the auger, the casing shall be filled with pea gravel or sand, and the ends shall be blocked and mortared shut (refer to City casing pipe detail).
- 2) Cover Depth: All sanitary sewer and services must have a minimum cover of four (4) feet.
- 3) Calculations: Provide calculations to substantiate the available capacity of the receiving sewer.
- 4) Drop Connections: Exterior drop connections will be permitted only where site conditions are not conducive for an elevation drop of less than two (1) foot. Interior drop connections will not be permitted (refer to City new drop manhole detail(s)).
- 5) Manhole Spacing: Manholes shall be provided at:
 - 400’ minimum intervals.
 - Change in pipe diameter
 - Change in pipe material
 - Change in grade
 - Change in horizontal alignment
- 6) Manhole Sizing: Sanitary sewer manholes shall have a minimum inside diameter of four (4) feet (refer to City sanitary manhole detail).
- 7) Separation Requirements: A minimum ten (10) foot horizontal separation shall be established between the sewer and any proposed or existing water distribution facility, or the invert of the water main shall lie a minimum of 18” above the top of the sewer pipe. Where neither of the above conditions can be met, the water main shall be encased for the duration of the horizontal conflict (10’ on each side of a perpendicular conflict), or the sewer shall be constructed of water main quality materials for the duration of the conflict (10’ on each side of a perpendicular conflict).
- 8) Services, Domestic: Domestic sanitary services shall be constructed of PVC SDR 26 with a minimum diameter of 6”. All domestic services shall connect to the public sewer with a wye fitting. A cleanout shall be installed within (10) feet of the structure.
- 9) Services, Industrial & Commercial: Industrial and commercial sanitary services shall be constructed of PVC SDR 26 or 21 with a minimum diameter of 6”. All industrial and commercial services shall connect to the public sewer at a manhole, and an inspection

manhole shall be provided within (10) feet of the structure (refer to manhole details for service connections).

- 10) Sewer Pipe, Materials (gravity): Sanitary sewer shall be constructed of the following materials:
 - i) Depth less than 20': PVC SDR 26 or Ductile Iron Pipe, Class 52
 - ii) Depth greater than 20': PVC SDR 21, or Ductile Iron Pipe, (class to be specified by depth, and manufacturers specifications)

- 11) Sewer Pipe, Minimum Size: Public sewer may have a minimum diameter of 8", and must provide a minimum self-cleaning flow velocity of 2 fps.

- 12) Force Main: Sanitary sewer force main shall conform to the following:
 - i) 4" minimum diameter
 - ii) Ductile Iron Pipe, Class 52 or PVC SDR 21 with Poly-wrapping
 - iii) Clean-outs at all vertical and/or horizontal bends, or at 700' minimum intervals in a manhole. Cleanouts will be installed via the use of a "T" connection with a cap at the top of the cleanout.
 - iv) Minimum flow velocity of two (2) fps
 - v) Air release valve shall be located at the high point of the force main.

- 13) Trench Backfill: All utility and service trenches within (3) feet of paved surfaces, or at a distance specified by the Engineer, shall be backfilled with CA-7 (Virgin Crushed Limestone). FA-6 (clean beach sand) material shall be used in all other unpaved locations. All Backfill material shall be properly compacted unless otherwise directed by the appropriate Engineering Division. Backfill under existing pavements, where an open cut of the pavement has been approved, shall be Flowable Fill that meets the IDOT standards of Controlled Low Strength Material (CLSM) Mixture #1. No fly ash will be permitted in this mix (refer to City pipe trench detail).

- 14) Lift Station: Lift stations will be permitted only where site conditions do not allow for the construction of a functional gravity sewage collection system. Where lift stations are permitted, the following criteria shall be met:
 - i) A lift station design report shall be submitted for review (*Contact the City of St Charles appropriate Engineering Division for sample report and/or additional information, see Section 6 for phone numbers*).
 - ii) A complete set of shop drawings and product specification information (i.e.: generator, pump, lift station...) shall be provided to the City for review.
 - iii) A detailed plan depicting the proposed layout of the lift station, including the location of the generator, control panel, wet and dry wells, access drive, and fencing, lighting, and landscape features shall be submitted for review.
 - iv) A natural gas powered emergency generator shall be provided.
 - v) A communication connection to the main Sewage Treatment Plant alarm system shall be provided.

vi) A dedicated lot and access drive shall be provided to the City.

- 15) Extension of Sewer System: Sanitary sewer system must be extended as a minimum, to the limit of the development at a minimum slope for self-cleaning velocity. Note on plans which sewer lines are to be public and private. Sanitary sewers shall be designed to accept all existing and future demand, based on the fully developed state under present zoning and the City's Comprehensive Plan.
- 16) Disconnection of Existing Services: Disconnection of existing services at their respective mains shall be by means of cutting out existing wye or tee and replacing with a straight piece of equal size pipe and making the final connection with "non-shear" mission couplings. Disconnection of all services must be performed prior to the demolition of an existing structure. Existing services to be abandoned shall be filled or removed.
- 17) Connecting to an Existing Sewer: When connecting to an existing sewer main by means other than an existing "Y", "T", or an existing manhole, one of the following methods shall be used:
- i) Using pipe cutter, neatly and accurately cut out desired length of pipe for insertion of proper fittings. Use "band-seal" couplings or similar couplings, and non-shear rings and clamps to fasten the inserted fittings and hold it firmly in place. Mission couplings shall have the length of boot approximately equal to the pipe diameter. Follow manufacturer's recommendations for the installation. No cut-in connection, made by breaking or cutting a hole in the main and inserting the spigot end of an ordinary sewer pipe shall be permitted.
 - ii) Circular, saw-cut of sewer main with proper tools ("Shower-tap" machine or similar) and proper installation of hub-"Y" saddle or hub-"T" saddle, in accordance with manufacturer's recommendations. This method shall only be allowed for pipe sizes over 12 inches in diameter. All must be encased in concrete flowable fill.
- 18) Structures Located Within the Floodplain: Sanitary sewer manholes constructed on the flood plain must have a rim two feet (2') above the base flood elevation or have a water-tight-lock-type frame and cover, Neenah R-1916 C or approved equal.
- 19) Video Note on All Plans: Engineering plans must contain the following note: "A current color video record and a type written transcription of the internal inspection of the newly constructed sewer system shall be submitted prior to refunding of site improvement escrow retention monies by the City of St Charles. All public mains shall be videotaped. The contractor must rotate the lens of the camera to look at all services. The service connections must be noted in the television report. When the proposed sanitary sewer system is to connect to an existing sanitary sewer system abutting the property, the existing sewer must also be televised and reported. The contractor shall coordinate the televising of existing contiguous sewers with the City of St Charles. All lines shall be flushed and cleaned prior to videotaping."

20) Connecting to an Existing Structure: Pipe penetrations into existing sanitary manholes shall be properly sized and cored and sealed with flexible watertight connections (refer to City sanitary sewer connection to existing manhole detail).

21) Separation Requirements: Sanitary and storm sewer utility services shall be separated by a minimum ten feet (10') of horizontal separation.

B: Materials:

1) Drop Connections: Drop connections shall be constructed of Ductile Iron Pipe, Class 52 or PVC SDR 26, per manufactures specifications. All drop manhole piping shall be encased in concrete (refer to standard drop manhole detail).

2) Frame & Lid: Frame: *Neenah R-1713 or R-1916C in Floodplain*
Lid: *Neenah R-1713 or R-1916C type "B" with the words "City of St. Charles - SANITARY" cast into surface.*

3) Joints: All joints shall conform to ASTM D-3212 for PVC pipe and ASTM A-746 for ductile iron. Both pipe types shall be joined by means of a flexible gasket. Gaskets for PVC joints shall be in conformance with ASTM A 21.11-79 (AWWA C111).

4) Manhole: New sanitary manholes are to be precast reinforced concrete eccentric type with a minimum 48" I.D. barrel section; Cone sections shall have a 3 inch integrally cast precast concrete collar; Pipe penetrations are to be sealed via the use of a cast in place flexible synthetic rubber pipe sleeve which is to be fastened to the pipe with two stainless steel bands. Barrel sections shall be sealed using (2) butyl rubber strips per tongue and groove section. Chimney seals are to be internal type, manufactured by "Cretex" or approved equal by Public Works. All new or adjusted steps shall be made of steel reinforced plastic, using an approved plastic meeting ASTM D4101, Type II, Grade 49108 over a #3 Grade 60, ASTM A615, reinforcing bar. A maximum of 8" of adjusting rings shall be used (refer to standard sanitary manhole detail).

5) Services: Sanitary services shall be constructed for all build-able lots. Services shall be constructed of PVC SDR 26 pipe, six (6) inch minimum diameter, and shall be extended to the rights-of-way limits. All connections to the public main shall be at a manhole or at a "wye" fitting approved by Public Works Division. Once installed all services extending to the City right-of-way limits shall be located utilizing a 2" x 4" wooden stake painted red.

6) Sewer Pipe, Materials: Sanitary sewer shall be constructed of the following materials:

- Depth less than 20': PVC SDR 26 or Ductile Iron Pipe, Class 52
- Depth greater than 20': Ductile Iron Pipe, Class 52 or PVC SDR 21
- Force Main: Ductile Iron Pipe, Class 52 or PVC SDR 21

- 7) Thrust Blocks (force main): Thrust blocking shall be a combination pre-cast masonry blocks and “*Mega-lug*” brand restraints.

- 8) Trench Backfill: All utility and service trenches within (3) feet of paved surfaces, or at a distance specified by the Engineer, shall be backfilled with CA-7 (Virgin Crushed Limestone). FA-6 (clean beach sand) material shall be used in all other unpaved locations. All Backfill material shall be properly compacted unless otherwise directed by the appropriate Engineering Division. Backfill under existing pavements, where an open cut of the pavement has been approved, shall be Flowable Fill that meets the IDOT standards of Controlled Low Strength Material (CLSM) Mixture #1. No fly ash will be permitted in this mix (refer to City pipe trench detail).

SECTION II

STORM SEWER SYSTEM

A. DESIGN REQUIREMENTS

B. MATERIALS

A: Design Requirements:

- 1) Auger: Augering will be required at all roadway crossings unless otherwise permitted by the City of St Charles appropriate Engineering Division. Steel casing and “Cascade” spacers (or approved equal) shall be utilized. Following completion of the auger, the casing shall be filled with pea gravel or sand, and the ends shall be blocked and mortared shut (refer to City casing pipe detail).
- 2) Catch Basins: Catch basins shall consist of four (4) foot minimum interior diameter reinforced concrete structures with a 3’ sump (refer to restrictor structure detail).
- 3) Cover Depth: All storm sewer and sump lines must have a minimum cover of two (2) feet.
- 4) Video Note on All Plans: Engineering plans must contain the following note: “A current color video record and a type written transcription of the internal inspection of the newly constructed sewer system shall be submitted prior to refunding of site improvement escrow retention monies by the City of St Charles. All public mains shall be videotaped. The contractor must rotate the lens of the camera to look at all services. The service connections must be noted in the television report. When the proposed sanitary sewer system is to connect to an existing sanitary sewer system abutting the property, the existing sewer must also be televised and reported. The contractor shall coordinate the televising of existing contiguous sewers with the City of St Charles. All lines shall be flushed and cleaned prior to videotaping.”
- 5) Disconnection of Existing Services: shall be by means of cutting out existing “wye” or tee and replacing with a straight piece of equal size pipe and making the final connection with “non-shear” mission couplings. Disconnection of all services must be performed prior to the demolition of an existing structure.
- 6) Flared End Sections: All flared end sections greater than or equal to 12 inches, that will receive or discharge storm water, shall have a removable grate system to prevent entry. This grate system shall be made from steel stock that is hot-dipped galvanized after fabrication.
- 7) Extension of Sewer System: The storm sewer must be extended to the limits of the subdivision or lot and must be sized to accept all tributary areas.
- 8) Capacity Calculations: Provide calculations to substantiate the available capacity of the existing receiving storm sewer/stream in light of the design discharge from the proposed development. Note on all plans which sewer lines are to be public and private. All proposed storm sewer systems shall be designed for a 10-year storm event per the Kane County Stormwater Ordinance as adopted and modified by the City of St. Charles.
- 9) Connecting to an Existing Sewer: When connecting to an existing sewer main by means other than an existing “Y”, “T”, or an existing manhole, one of the following methods shall be used:

- a. Using pipe cutter, neatly and accurately cut out desired length of pipe for insertion of proper fittings. Use “band-seal” couplings or similar couplings, and shear rings and clamps to fasten the inserted fittings and hold it firmly in place. Mission couplings shall have the length of boot approximately equal to the pipe diameter. Follow manufacturer’s recommendations for the installation. No cut-in connection, made by breaking or cutting a hole in the main and inserting the spigot end of an ordinary sewer pipe shall be permitted.
- b. Circular, saw-cut of sewer main with proper tools (“Shewer-tap” machine or similar) and proper installation of hub-“Y” saddle or hub-“T” saddle, in accordance with manufacturer’s recommendations. This method shall only be allowed for pipe sizes over 12 inches in diameter. All must be encased in concrete flowable fill.

10) Frame & Grate: Frames and grates shall be provided as appropriate for the structure location (i.e.: depressed curb, barrier curb, overflow route, rear yard...). All grates to be located near a paved surface shall be “bicycle safe”. Calculations may be required to demonstrate that the proposed grates allow for an inflow that does not exceed the design capacity for the downstream pipe (refer to standard details).

11) Inlets: Inlets shall consist of a two (2) foot minimum interior diameter reinforced concrete structure. Inlets shall be placed at the sag of vertical curves in roadways, at low points in parking areas, and at other locations as necessary to minimize stormwater ponding and/or flow across roadways or intersections. Storm sewer inlets shall be placed not more than 500’ apart in pavement and shall not exceed 250’ in grassy areas.

12) Release Structure / Restrictor: The release structure shall be of a weir wall orifice design (refer to overflow weir structure detail) or as approved by the City of St. Charles.

13) Underground Storage System

- a. Underground chambers must be large enough to allow the chamber to be manually cleaned.
- b. Access points for ingress and ventilation purposes are to be provided in the chamber at a maximum spacing of 100 feet and at the ends of the chamber.
- c. Underground storage chambers are to be clearly labeled on the engineering plans as “Private Storm Water Storage Facility.” These chambers are to be maintained by the developer until a owners association has been established.
- d. Poured in place reinforced concrete chamber designs must be signed and sealed by an Illinois Licensed Structural Engineer.
- e. All reinforcement steel shall be epoxy coated and all concrete shall be treated with a protective concrete coating, on the interior and exterior of the chamber.
- f. For precast concrete construction, geo-textile fabric must be placed over the top of the structure, and all joints must be grouted.
- g. All structural steel members used shall be Corten or hot dipped galvanized. All connections shall have a like treatment.
- h. A minimum of 12 inches of topsoil plus sod must be placed to cover the underground storage facility when constructed under pervious surface.

- 14) Separation Requirements: A minimum ten (10) foot horizontal separation shall be established between the sewer and any proposed or existing water distribution facility, or the invert of the water main shall lie a minimum of 18” above the top of the sewer pipe. Where neither of the above conditions can be met, the water main shall be encased for the duration of the horizontal conflict (10’ on each side of a perpendicular conflict), or the sewer shall be constructed of water main quality materials the duration of the conflict (10’ on each side of a perpendicular conflict).
- 15) Sewer Pipe, Minimum Size: Public sewer shall have a minimum diameter of 10” for the first “run” of pipe, 12” minimum for all other.
- 16) Slope: Slope shall be adequate to provide a minimum flow velocity of 3 fps and maximum acceptable velocity is 10 fps.
- 17) Structure Sizing: Manholes and catch basins shall have a minimum inside diameter of four (4) feet for sewer pipe 18” or less in diameter, five (5) feet for sewer pipe 21” to 48” in diameter. Pipes larger than 48” in diameter will require a special design (refer to standard manhole and catch basin details)
- 18) Structure Spacing: Manholes / Catch basins shall be provided at:
- 400’ minimum intervals.
 - Change in pipe diameter.
 - Change in pipe material.
 - Change in vertical alignment.
 - Change in horizontal alignment.
- 19) Sump Lines: Domestic sump services shall be constructed of PVC SDR 26 with a minimum diameter of 4”. All domestic services shall connect to the public sewer by removing a section of main and installing a new “wye” fitting for pipes less than 15” in diameter, “Kor-N-Tee” Boots for pipes 15” and larger, or at a structure (refer to connection detail).
- 20) Trench Backfill: All utility and service trenches within (3) feet of paved surfaces, or at a distance specified by the Engineer, shall be backfilled with CA-7 (Virgin Crushed Limestone). FA-6 (clean beach sand) material shall be used in all other unpaved locations. All Backfill material shall be properly compacted unless otherwise directed by the appropriate Engineering Division. Backfill under existing pavements, where an open cut of the pavement has been approved, shall be Flowable Fill that meets the IDOT standards of Controlled Low Strength Material (CLSM) Mixture #1. No fly ash will be permitted in this mix (refer to City pipe trench detail).
- 21) Underdrains: Underdrains will be required under curbs at the bottom of all roadway sags. Underdrains shall extend 50 feet on each side of the inlet. Underdrains shall be perforated polyethylene pipe. The underdrain shall be encased in gravel trench with no fines, and a geotextile fabric shall be used to limit sedimentation in the pipe (refer to standard “Pipe Underdrain” detail).

- 22) Sump Lines: Storm services shall be constructed for all buildable lots. Services shall be constructed of PVC SDR 26 pipe, six (6) inch minimum diameter, and shall be extended to the rights-of-way limits. All connections to the public main shall be at a manhole or at a “wye” fitting approved by Public Works Division. Once installed all services extending to the City right-of-way limits shall be located utilizing a 2” x 4” wooden stake painted green.
- 23) Culverts: Culvert pipe designs shall be in accordance with the Illinois Department of Transportation “Standard Specification for road and Bridge Construction” latest edition. Publicly owned culver pipes shall be PVC for pipes less than 15” in diameter or RCP for pipes equal to 15” or larger in diameter.

B: Materials:

- 1) Casing: Where water main protection is required, encasement shall consist of PVC SDR 26, or steel casing with “*Cascade type CCR-STD*” spacers or approved equal.
- 2) Frame & Grate:
- | | | |
|-------------------------------|------------|--------------------------------------------|
| Curb Inlet/C.B.: | High back: | <i>Neenah R-3281-A or R-3278-1</i> |
| | Depressed: | <i>Neenah R-3506-A2</i> |
| C.B., “behind the curb type”: | | <i>Neenah R-3305</i> |
| | | <i>Neenah R 1713 (Refer to Lid Detail)</i> |
| C.B./M.H., Type “D”: | Grate: | <i>Neenah R 1713 (Refer to Lid Detail)</i> |
| | Frame: | <i>Neenah R-1713</i> |
| C.B., “beehive type”: | | <i>Neenah R-4340-B</i> |
- 3) Manhole: Manholes shall be reinforced concrete with steps provided 16” on-center. All manholes shall have a minimum inside diameter which conform to the following:
- 18” storm sewer and smaller - four (4) foot inside diameter
 - 21” to 48” storm sewer - five (5) foot inside diameter
 - Larger than 48” storm sewer - special design required
- 4) Sewer Pipe, Materials: Main line storm sewer shall be constructed of one of the following:
- a. Pre-cast reinforced concrete pipe, with “O-ring” joints;
 - b. PVC pipe, rigid, (Min. SDR 26, push-on gasket joints);
 - c. All joints shall conform to ANSI 21.11 for ductile iron pipe.
 - d. Ductile iron pipe, (Class 52), minimum;
 - e. HDPE pipe, (Rigid with corrugated exterior and smooth interior meeting AASHTO M-294, Type S. Pipe sections shall be joined with PVC double bell couplers installed on the pipe with O-ring gaskets. Ex-filtration standards shall meet or exceed that of PVC SDR 26 with push-on-joints.) **FOR PRIVATE USE ONLY. NOT TO BE**

USED WITHIN PUBLIC RIGHT-OF-WAY OR FOR PUBLICLY OWNED AND MAINTAINED STORM SEWER

- f. The type of pipe material will be dependent upon the depth of bury, soil conditions, and pipe criteria, and as approved by the City of St. Charles.
 - g. For RCP/CSP pipe, lifting holes shall not be allowed on pipes less than 84” in diameter.
 - h. All storm sewer smaller than 15-inches in diameter that will be publicly owned and maintained shall be PVC pipe, rigid, (Min. SDR 26, push-on gasket joints).
- 5) Flared End Section: Flared end sections and subsequent riprap material shall be designed and specified per the Illinois Department of Transportation “Standard Specification for road and Bridge Construction” latest edition. Flared end sections shall constructed of a concrete material only or approved by the appropriate Engineering Division.

SECTION III

STORM WATER MANAGEMENT /SITE GRADING

- A. DESIGN RESTRICTIONS**
- B. DESIGN REQUIREMENTS**
- C. MATERIALS**

A: Design Restrictions:

- 1) High Water Level: The proposed grading conditions shall not result in conditions that will cause water to pond on adjacent property or to rise within (2) feet of any existing or proposed top of foundation elevations or low opening of a structure.
- 2) Off-site Grading: Off-site grading will not be permitted unless permission in the form of an easement is obtained from the subject property owner.
- 3) Release Rates: Storm water release rates shall at a minimum meet or exceed the Kane County Stormwater Ordinance as adopted and modified by the City of St Charles.
- 4) Watershed boundaries: Proposed construction may not result in any modification to existing watershed boundaries or the alteration of off-site drainage patterns.
- 5) Wetlands: Existing wetlands may not be altered without an authorized permit from the Army Corps of Engineers, as well as consent from FEMA, the IEPA, and the Department of Natural Resources, Office of Water Resources.

B: Design Requirements:

- 1) Detention Basins (Dry basins): Shall meet or exceed the Kane County Stormwater Ordinance as adopted and modified by the City of St Charles.
- 2) Detention Basins (Wet basins): Shall meet or exceed the Kane County Stormwater Ordinance as adopted and modified by the City of St Charles.
- 3) Flared End Section: Flared end sections shall be required in any areas where a storm sewer discharges into a detention basin. Trash grates shall be provided on all flared end sections 12 inches in diameter and greater. Permanent erosion control shall be provided with riprap at all flared end sections. Temporary erosion control in the form of straw bales shall be provided at all outlet flared end sections, and shall be maintained until the topsoil has been adequately stabilized with vegetative cover. All flared end sections greater than or equal to 12 inches, that will receive or discharge storm water, shall have a removable grate system to prevent entry. This grate system shall be made from steel stock that is hot-dipped galvanized after fabrication.
- 4) Green Space, Slope Requirements: Green space slopes shall conform to the following:
 - 4:1 maximum slope
 - 2% minimum slope
 - Where retaining walls are required, a registered Illinois Structural Engineer must sign the plans if the proposed height is four (4) feet or higher.

- 5) Inlet Ponding, Maximum Levels: The engineer shall calculate the 100 year water surface elevations for the stormwater storage facilities. Inlet ponding in excess of one (1) foot during a 100-year event will not be permitted. The overflow route and limits of ponding shall be clearly illustrated on the plans. Paved parking lots may not be utilized to provide any portion of the required site run-off storage volume.
- 6) Overflow: An overflow drainage route must be established. All storm water management facilities shall have a clearly defined and protected overflow route illustrated with an overflow elevation and a large arrow. The overflow routes through the subdivision shall also be illustrated with large arrows, and spot elevations shall be shown at 50' intervals along the route.
- 7) Pavement, Slope Requirements: Pavement slopes shall conform to the following:
 - 1% minimum and 5% maximum slope (pavement)
 - 0.5% minimum slope (curb & gutter)
 - 8% maximum slope (driveways only)
- 8) Release Rate: Shall meet or exceed the Kane County Stormwater Ordinance as adopted and modified by the City of St Charles.
- 9) Release Structures: Shall meet or exceed the Kane County Stormwater Ordinance as adopted and modified by the City of St Charles.
- 10) Stormwater Management Report: A Stormwater Management Report shall be submitted to the City for review. The report shall include the following:
 - All appropriate permit forms, associated fees need be submitted.
 - A narrative that discusses topographical conditions, soil conditions, analysis methodology, modeling results, and conclusions.
 - Data from an analytical modeling program which features hydrograph methodology, TR20 or equal.
 - A critical duration analysis shall be performed which analyzes the proposed topographic and drainage conditions for the 2, 6, 12, 18, and 24 hour durations of the 100 year rainfall. Hydrograph methodology shall be used in cooperation with projected rainfall data as documented in the "Bulletin 70 Huff Distribution Curve". The largest storage volume that is produced from this analysis shall be the required volume for the development.
 - Basin sizing calculations; required and proposed stormwater storage volumes.
 - Stormwater release structure calculations including proposed, required, and existing release rates.
 - Exhibits which illustrate the following:
 - Existing conditions (i.e.: topography, buildings / structures, water bodies, roadways...).
 - Proposed conditions (i.e.: topography, lot alignments, top of foundation elevations, roadways, drainage ways, stormwater storage facilities, overflow routes...).
 - Existing and proposed watershed boundaries and ridgelines.

- Proposed 100-year water surface elevation and high water level.

11) Topography: A drainage plan shall be provided which includes the following:

- One (1) foot contours.
- Easements, including dimensions and easement type.
- Proposed storm water storage facilities.
- Existing water bodies and drainage features.
- Proposed roadways and rights-of-way's.
- Proposed lot alignments and lot numbers.
- Proposed top of foundation elevations.
- Overflow drainage routes and 100-year water surface elevations with cross sections.
- Proposed basin volumes, 100-year water surface elevations, and high waster levels.
- Storm sewer appurtenances.
- Proposed elevations at all lot corners and along all break points at side yards.

C: Materials:

- 1) Casing: Where water main protection is required, encasement shall consist of PVC SDR 26, or steel casing with “*Cascade type CCR-STD*” spacers or approved equal.
- 2) Flared End Section: Flared end sections shall be required in any areas where a storm sewer discharges into a detention basin. Trash grates shall be provided on all flared end sections 12 inches in diameter and greater. Permanent erosion control shall be provided with riprap at all flared end sections. Temporary erosion control in the form of straw bales shall be provided at all outlet flared end sections, and shall be maintained until the topsoil has been adequately stabilized with vegetative cover. All flared end sections greater than or equal to 12 inches, that will receive or discharge storm water, shall have a removable grate system to prevent entry. This grate system shall be made from steel stock that is hot-dipped galvanized after fabrication.

SECTION IV

WATER SYSTEM

- A. DESIGN RESTRICTIONS**
- B. DESIGN REQUIREMENTS**
- C. MATERIALS**

A: Design Restrictions:

- 1) Dead End Water Main: The construction of dead end water main will not be permitted. Where dead end mains cannot be avoided on a temporary basis, a fire hydrant shall be placed at the end.
- 2) Pipe Compound: Pipe compound will not be permitted in any water main construction, including service connections. A general note to this effect shall be included in the Final Engineering Plans.

B: Design Requirements:

- 1) Tunneling: Augering or directional drilling will be required at all roadway crossings unless otherwise permitted by the City of St Charles appropriate Engineering Division. Steel casing and “Cascade” spacers shall be utilized exclusively. Following completion of the auger, the casing shall be filled with pea gravel or sand, the ends shall be blocked and mortared shut, or have end boots installed.
- 2) Cover Depth: All water main, hydrant leads, and services must have a minimum cover of five (5) feet, and a maximum cover of (10) feet. Variations from these standards will require approval of appropriate Engineering Division.
- 3) Fire Flows: Fire flows shall be calculated at a twenty (20) psi residual pressure and shall be available for a minimum four (4) hour continuous duration for flows above 2,000 gpm, and a two (2) hour continuous duration for flows below 2,000 gpm. Appropriate water pressure and flow must be provided in accordance with the St. Charles Municipal Code, Ord. 15.28.060:
 - Single family Detached Residential: 1,000 - 1,500 gpm
 - Town / Row or Cluster Housing: 1,500 - 2,000 gpm
 - Apartment Type Construction: 3,000 - 4,000 gpm
 - Industrial & Storage: 3,000 - 5,000 gpm
 - Research & Development Laboratories: 3,000 - 4,000 gpm
 - Business & Commercial Areas: 3,000 - 4,500 gpm
 - Mercantile Centers: 3,000 - 6,000 gpm
 - Assembly & Education: 3,000 - 5,000 gpm
 - Health Care & Institutional: 3,000 - 4,000 gpm
- 4) Hydrant Leads: All hydrant leads must be constructed of DIWM CL 52 with a minimum diameter of 6”. Where hydrant leads are longer than 100’, 8” diameter DIWM will be required.
- 5) Hydrant Spacing: Hydrants must be placed at a minimum of 400-foot intervals, and may not be less than five (5) feet from the back of curb. No buildable area shall be farther than 300’ from a fire

hydrant, and a minimum of one hydrant shall be located at each intersection. For larger projects, hydrants shall be proposed at high points for air release. All hydrant locations shall be coordinated with the City of St. Charles Fire Department and appropriate Engineering Division.

- 6) Horizontal and Vertical Separation: - Watermains and Sewer horizontal and vertical separations shall conform to the latest version of the “Standard Specifications for Water & Sewer Construction in Illinois. Reference to these standard and specification should be made when it is impossible to meet separation requirements for casing pipe requirements (refer to standard casing pipe detail).
- 7) Abandoning and Replacing Existing Services: All existing services shall be abandoned at the corporation stop (close corporation stop, cut services, and install copper disk). Existing services should be replaced from the new main to the B-Box if service is lead. If service is copper, it should be cut and tapped into the new main. Approved trench backfill material is to be placed where any trench lies within (3) feet of the edge of pavement, curb, or sidewalk. It is assumed all lines are lead and must be replaced to B-Box.
- 8) Interruption of Water Usage: Water services may only be interrupted when the transfer of services to the new main takes place. Services shall be transferred subsequent to testing and chlorination of the proposed main. The contractor shall contact the St. Charles Water Division at 1-630-377-4405 prior to transfer of service. Residents and Businesses must be informed a minimum of 24 hours in advance of any interruption by the City of St. Charles Water Division staff.
- 9) Services, Domestic: Domestic water services shall be prided to each lot. The minimum size for domestic services is (1) inch. Once installed all services extending to the City right-of-way limits shall be located utilizing a 2” x 4” wooden stake painted blue.
- 10) Services, Fire Protection: Where fire protection services are required, separate domestic and fire protection services shall be provided. Each service must have an independent tie into the public water main.
- 11) Thrust Blocking: Preformed concrete block thrust blocking shall be provided at all bends greater than 10 degrees, at all mechanical joint connections, and at all fire hydrants (refer to city thrust blocking detail).
- 12) Trench Backfill: All utility and service trenches within (3) feet of paved surfaces, or at a distance specified by the Engineer, shall be backfilled with CA-7 (Virgin Crushed Limestone). FA-6 (clean beach sand) material shall be used in all other unpaved locations. All Backfill material shall be properly compacted unless otherwise directed by the appropriate Engineering Division. Backfill under existing pavements, where an open cut of the pavement has been approved, shall be Flowable Fill that meets the IDOT standards of Controlled Low Strength Material (CLSM) Mixture #1. No fly ash will be permitted in this mix (refer to City pipe trench detail).
- 13) Valve Spacing: Right-hand closing resilient wedge gate valves at intervals not over 600 feet intervals.

- 14) Valve Vaults: Valve vaults are to be precast reinforced concrete, eccentric type (refer to standard detail and materials section for sizing specifications). A maximum of (8-inches) of adjusting rings shall be used.
- 15) Frame and Covers: All valve vault structures shall have a Neenah Foundry Company R-1713 frame and type “B” Lid with concealed pick hole. Lids shall be furnished with “City of St. Charles - Water” cast into the top surface (refer to City standard detail).
- 16) Water Main, Minimum Size: The minimum size for any public water main shall be 8” (with the exception of hydrant laterals that may be 6”, (see design requirement #3 above for fire flow considerations).
- 17) Separation: A ten-foot horizontal separation shall be maintained between water mains and appurtenances, and all other utilities, public or private.
- 18) Appurtenance Separation: Water appurtenances shall be a minimum of (20) feet from permanent structures; this applies to any structure that may require a building permit (i.e. retaining walls, pools, shed, garages, etc.)
- 19) Dead Ends: Dead end water mains longer than 300’ should not be permitted. The water system must be extended, as a minimum, to the limits of the development and looped wherever possible. Note on all plans which mains are to be public and private.
- 20) Adjustment of Structures: All adjustments to valve vaults shall be made with precast concrete adjusting rings not to exceed a maximum of eight (8) inches overall in height. Watertight valve vaults shall be provided for each valve. Barrel sections shall be seated using (2) butyl rubber strips per tongue and groove section. Valve vaults are to be precast reinforced concrete, concentric type (refer to standard detail and materials section for sizing specifications). After final adjustments have been made, all joints in precast structures shall be mortared. The mortar shall be composed of one part cement to three parts sand, by volume, based on dry metals and shall be thoroughly wetted before laying. Vaults may only be extended to a maximum of 23” from the surface to the inside flare of the manhole cone section.
- 21) Connecting to Existing Water Mains: Connection to the end of an existing a water main shall be with a valve only. No new water main should be connected to the existing water main unless the new water main can be pressure tested separately. Connection to an existing water main shall be done by pressure connection only unless authorized by the appropriate Engineering Division. Pressure connection and valve shall be located within the valve vault. No pressure connection shall be within 3 feet of an existing water main joint. If pressure connection cannot be done, use a cut in sleeve and tee connection. All fittings will be swabbed out with a chlorine solution of at least 50 mg/L. A City Representative must test this solution.
- 22) Service Taps: Service taps to water mains are not permitted until after bacteriological sampling and analysis has been completed to the satisfaction of the appropriate Engineering Division. No water service connection shall be made by any person or firm other than a State

of Illinois licensed contractor, with a State of Illinois licensed plumber on the job, bonded with the City.

- 23) Landscaping: Landscape plantings shall not interfere with operation and maintenance of water appurtenances. Trees shall be placed no closer than (10) feet from any structure(s).
- 24) Fire Hydrants: Fire hydrants shall be installed with a maximum of one extension kit used, and a maximum extension of 36". Fire hydrant extension kits must be of the same manufacture as the hydrant, and must be installed according to the manufacturers specifications.
- 25) Joint Restraint: All mechanical joint fittings shall have restraining glands installed. Restraint device shall be Uni-flange by Ford Company or Mega-lug by EBAA Iron. Push joint pipe restraint shall be Field Lock Gaskets by US Pipe or Series 1700 Mega-lug or Series 1390 Pipe Restraint by Ford. Lengths of pipe restraint shall be determined from manufacturers installation specifications (refer to watermain restraint detail).

C: Materials:

- 1) Corporation Stops:
 - a. Compression fittings.
 - i. Mueller B-25008 (¾"-1"-1 ½"-2")
 - ii. Ford
 1. FB1000-4-Q 1"
 2. FB1000-6-Q 1 ½"
 3. FB 1000-7-Q 2"
 - iii. A. Y. McDonald 4701-BQ (1", 1 ½", 2")
 - iv. Q Series Brass
- 2) Curb Stops:
 - a. Compression fittings.
 - i. Mueller B-25155 (¾"-1"-1 ½"-2")
 - ii. Ford
 1. B-44-444-Q 1"
 2. B44-666-Q 1 ½"
 3. B-44-777-Q 2"
 - iii. A. Y. McDonald 6104-Q (1", 1 ½", 2")
 - iv. Q Series Brass
- 3) Curb Box: (Minneapolis pattern, lid marked "WATER")
- 4) Buffalo Type:
 - a. For 1" thru 2", Mueller H-10300 Copper service
 - b. A. Y. McDonald, 5615 1 ¼"

- 5) Fire Hydrant:
 - a. Approved Models: (Refer to standard Fire Hydrant Detail)
 - i. Mueller Super Centurion 200
 - ii. Waterous Pacer Model WB-67-250
 - iii. Clow Medallion
 - iv. All hydrants shall have:
 1. 6” mechanical joint connection
 2. 5 ¼” valve opening
 3. 5” cover over hydrant lateral
 4. 6” valve on lateral
 5. “Hydrfinder” standard hydrant locator, installed
 6. Valve box shall have a valve box stabilizer installed *
*(Valve box adaptor #2 type A, as made by Adaptor, Inc. or approved equal)

- 6) Fire Hydrant Paint: Safety Red, Sherwin Williams ‘Shercryl’ 6403-31922, B66R300

- 7) Bolts Placed Underground: All below grade factory installed bolts and fasteners shall be 304-grade stainless steel.

- 8) Valves: 4” through 16” diameter” Right-hand closing Resilient Wedge gate valves, conforming to AWWA Standard C-509 as manufactured by the Clow Corporation, Waterous Company or approved equal. All below grade factory installed bolts and fasteners shall be 304-grade stainless steel.

- 9) Valve Vaults: Watertight valve vaults shall be provided for each valve. Barrel sections shall be sealed using a butyl rubber or rubber strip (Refer to City standard valve vault detail).
 - a. 3” through 6” valves..... Min. 4’ inside diameter vault minimum
 - b. 8” and larger valves..... Min. 5’ inside diameter vault minimum
 - c. Pressure Taps..... Min. 5’ inside diameter vault minimum
 - d. Valve Vault Lid..... Neenah R-1712, Type B or approved equal
 - e. The word “WATER” shall be cast into the surface of the lid.
 - f. Vaults are not required for hydrant auxiliary valves.
 - g. Water main with a bury depth greater than 6.0’ shall have steps installed in valve vaults.

- 10) Watermain Pipes:
 - a. Ductile Iron Class 52, conforming to AWWA Standard C-151.
 - i. Cement Lining, conforming to AWWA Standard C-104.
 - ii. Mechanical or push-on joints shall conform to AWWA Standard C-111.
 - iii. At minimum, Type 3 laying conditions shall be provided, conforming to AWWA Standard C-600 (Attached).
 - b. All watermains shall be encased in a High Density polyethylene encasement with its material specifications and installation method in accordance with ANSIAWWA C105/A21.5, ASTM A674, using “Method A” installation.

- c. All side yard and rear yard water mains not directly adjacent to public roadways or paved surfaces shall be Ductile Iron Pipe, Class 55 with a type 5 laying condition.
- d. Brass Wedges shall be installed to provide electrical conductivity.

11) Joint Restraint: All mechanical joint fittings shall have restraining glands installed. Restraint device shall be Uni-flange by Ford Company or Mega-lug by EBAA Iron. Push joint pipe restraint shall be Field Lock Gaskets by US Pipe or Series 1700 Mega-lug or Series 1390 Pipe Restraint by Ford. Lengths of pipe restraint shall be determined from manufacturers installation specifications (refer to watermain restraint detail).

12) Copper Service Lines:

- a. One-inch diameter minimum
- b. Type K copper tubing
- c. Compression fittings only

1-inch service connections only may be connected utilize the direct tap methods to 6-inch mains and larger only. If there is insufficient diameter water main to install a direct tap, then a saddle tap shall be allowed. Service taps of 1 ¼", 1 ½," & 2" require the use of a tapping saddle. Saddles shall be full circle, 304-grade stainless steel, with nylon washers and Nitrile gasket, as manufactured by Smith-Blair; model #372, or approved equal.

13) Tapping Sleeves:

- a. 4" through 8" diameter:
 - i. Romac SST-945 stainless steel or approved equal or Smith – Blair 665 stainless steel or approved equal, or Mueller H-615 cast iron or approved equal.
- b. 10" and larger diameter:
 - i. Mueller H-615 cast iron or approved equal.
 - ii. Flange fasteners shall be 304-grade stainless steel.

14) Casing pipe: Carrier pipe shall be centered within a casing by use of model CCS stainless steel casing spacers as manufactured by Cascade Waterworks Mfg. Of Yorkville, Illinois or prior approved equal. Fill with sand and brick at ends or install end boots.

15) Ductile Service Lines:

- a. Fire:
 - i. The first O. S. & Y. valve on the inside of the building must be in place for pressure testing, chlorination and sampling.
 - ii. Testing against flanges will not be allowed.
- b. Domestic:
 - i. The first permanent valve on the inside of the building must be in place for pressure testing, chlorination and sampling.
 - ii. Testing against flanges will not be allowed.

SECTION V

PAVEMENT / ROADWAYS

A. DESIGN REQUIREMENTS

A: Design Requirements:

- 1) Generally: Street Systems shall be designed to meet the requirements of the applicable jurisdiction (e.g., City, IDOT, KDOT, DUDOT, and ST Charles Township). Any proposed street dedication shall be in accordance with the following standards.
- 2) Right-of-way and Pavement Requirements:

Street Designation	Minimum R.O.W. Width	Minimum Street Width	Minimum Structural Number	Minimum Horizontal Centerline Radius	Minimum Tangent
Residential					
Estate	66 ft.	26 ft.	2.40	200 ft.	50 ft.
Local	66 ft.	33 ft.	2.90	200 ft.	50 ft.
Collector	80 ft.	39 ft.	3.65	300 ft.	100 ft.
Arterial	100 ft.	52 ft.	See Note 1	500 ft.	200 ft.
Industrial					
Local	66 ft.	40 ft.	3.00	200 ft.	50 ft.
Collector	80 ft.	44 ft.	See Note 1	300 ft.	100 ft.
Arterial	100 ft.	52 ft.	See Note 1	500 ft.	200 ft.

Note 1: Heavily traveled streets in industrial and residential areas shall be considered on an individual basis and pavement designs shall be based on specific engineering data for each street

Street Designation	Minimum Gradient	Maximum Gradient	Minimum Soil Support (I.B.R.)	Maximum A.D.T.
Residential				
Estate	0.5%	7.0%	3.0	400
Local	0.5%	7.0%	3.0	1,000
Collector	0.5%	5.0%	3.0	3,500
Arterial	0.5%	5.0%	3.0	10,000
Industrial				
Local	0.5%	5.0%	3.0	1,000
Collector	0.5%	5.0%	3.0	3,500
Arterial	0.5%	5.0%	3.0	10,000

- 3) Pavement Lengths:
 - a. Maximum residential block length shall be per title 16.08.030.
 - b. Cul-de-sac shall have a maximum length of as defined in Title 12.30.050(B)4

4) Pavements: Pavements shall be designed and constructed so as to obtain a minimum twenty (20) year service life with minimal maintenance after acceptance of the pavement by the City of St. Charles. The design engineer should consider such factors as construction and end use traffic loading sub-base IBR, etc., in determining the structural make up of the pavement section.

a. Pavement Materials and Minimum thickness: The following two pavement sections are the MINIMUM acceptable to the City. Their use must be supported by calculations to substantiate the use of the minimum pavement section.

i. Rigid Pavement

1. A minimum of 9” Portland Cement Concrete pavement (PCC) designed in accordance with IDOT standards. All Portland Cement Concrete shall be treated with a protective coat application.
2. Concrete pavements shall be reinforced in accordance with IDOT standards.
3. Concrete pavement shall have a minimum 4-inch of sub-base granular material, Type B. Milled asphalt meeting aggregate sub-grade specifications **cannot** be used for sub-base granular material, Type B.
4. Portland Cement Concrete shall have minimum 14-day compressive strength of 3500 psi.
5. In cases where an additional cross section may be needed for the sub-grade, the use of 9” of aggregate material meeting aggregate sub-grade gradation (i.e. crushed concrete) and a 3” milled asphalt cap may be used. Milled asphalt or the blending of asphalt millings with crushed concrete or other crushed aggregate material **is not allowed** for use in either the sub-grade or sub-base material.

ii. Flexible Base Pavement

1. Flexible base pavements shall have minimum of four inch (4”) Sub-base Granular Material, Type B. Milled asphalt meeting Aggregate Sub-grade specifications cannot be used for Sub-base granular Material Type B.
2. Hot-Mix Asphalt Base Course, 6”
3. Hot-Mix Asphalt Binder Course, IL-19.0, N50, 2 ¼”
4. Hot-Mix Asphalt Surface Course, Mix “C”, N50, 1 ½”
5. In cases where an additional cross section may be needed for the sub-grade, the use of 9” of Aggregate Material meeting Aggregate Sub-grade gradation 9 i.e. crushed concrete) and a 3” milled asphalt cap may be used. Milled asphalt or the blending of asphalt millings with crushed concrete or other crushed aggregate material **is not allowed** for use in either the sub-grade or sub-base material.

Note: All asphalt is to be laid by a self-propelled mechanical spreader.

b. Sub-grade: All sub-grade material shall have a minimum Illinois Bearing Ratio (IBR) of 3.0. All unsuitable sub-grade material, including sub-grade material having an IBR

less than 3.0 shall be removed and replaced with a suitable fill material, or the pavement must be designed to compensate for the soil condition. The soil support IBR values selected for use by the engineer shall represent a minimum value for the soil to be used.

- c. Pavement Design Shall Include: In addition to the information provided in the right-of-way and pavement requirements, pavement design shall include the following:
- i. Public Alleys shall be constructed of reinforced Portland Cement Concrete (PCC) designed in accordance to specifications listed above for rigid pavements.
 - ii. Maximum allowable pavement grade = 7% and minimum allowable pavement grade = 0.5%;
 - iii. Driveway grades shall have a minimum slope of 1% and a maximum slope of 8%. All driveway grades in excess of 5% shall substantiate that vehicular bottom clearances are met.
 - iv. Vertical curves shall be used when the absolute value of the algebraic difference between the intersecting pavements' centerlines exceed 1.5%. The minimum length of vertical curves shall be one hundred (100) feet for one and one-half (1.5) percent absolute value of the algebraic difference of grade. For each additional (1.0) percent, or fraction thereof, of absolute value of the algebraic difference in grade over one and one-half (1.5) percent, a fifty-foot increment, or fraction thereof, shall be added to the length of the vertical curve.
 - v. The minimum intersection curb radius:
 1. Two minor streets: 25'
 2. Minor and collector streets: 30'
 3. Tow collector streets: 40'
 4. Truck routes or zoned manufacturing: 45'
 - vi. Curb and gutter shall be a B-6.12 barrier type unless otherwise directed by the City of St. Charles appropriate Engineering Division. Curbs shall be constructed of 6.1 bag mix Portland Cement Concrete: 5-8% air entrained, (PCC) with (2), continuous epoxy coated, #4 rebar. A 1" expansion joints shall be placed at 60' intervals, and contraction joints shall be at 15' intervals and all points of curvature. All B-box, sanitary services and storm service locations shall be marked on the curb with a "W", "S" or "ST", as the case may be. All Portland Cement Concrete shall be treated with a protective coat application.
 - vii. 26-foot wide bituminous pavement shall have a 4" crown as measured from the flag of the curb. 26-foot wide concrete pavement shall have a 4" crown as measured from the flow line of the gutter.
 - viii. Pavement Patches

Note: All pavement patches shall be replaced in kind with the following revisions:

1. Flexible Pavement

Patches shall have a minimum of 6" Hot-Mix Asphalt Base Course, placed over a 4" compacted sub-base of granular material. 2 ¼" of Hot-Mix Asphalt Binder Course, IL-19.0, N50, and 1 ½" of Hot-Mix Asphalt Surface Course, Mix "C", N50 shall be laid subsequent to the Base Course. (See details for pavement patching).

2. Rigid Pavement

Concrete pavements shall be replaced with a minimum of 14 day, 3500 psi, 9" of Portland Cement Concrete mix placed over a 4" compacted granular sub-base. The existing pavement shall have #6 epoxy-coated dowel bars, 2' in length, drilled at 24" on center, grouted in place. All Portland Cement Concrete shall be treated with a protective coat application. (See details for pavement patching). PCC shall be a 6.1 bag mix, 5-8% air entrained.

3. Composite Pavement

For pavements with a concrete base and asphalt surface, the concrete shall be placed at the same thickness as the existing pavement, but shall be a minimum of 8" thick. #6 Epoxy-coated dowel bars, 2' in length, shall be placed at 24" on center, grouted in place

There shall be a minimum of 2 ½" surface asphalt placed over the concrete, Steel plates shall be placed over all Portland Cement Concrete patches until concrete is cured or a minimum of 3 days. (See details for pavement patching).

- ix. Storm inlets and catch basins placed within the roadway surface shall be designed to incorporate an under drain system of perforated PVC pipe in accordance with the attached detail.

5) Sidewalks:

- a. Public Sidewalks are to be constructed of a minimum of five (5) inch thick by five (5) feet wide, 6.1 bag mix Portland Cement Concrete (PCC) with (5-8%) air entrainment. All Portland Cement Concrete shall be treated with a protective coat application.
- b. Public walks that cross driveways are to be thickened to a minimum of (6) inches or the thickness of the driveway;
- c. Sidewalks shall be constructed of one (1) foot off the street R.O.W. line unless otherwise directed by the appropriate Engineering Division;
- d. Sidewalks shall be continuous through driveways.
- e. All utility service locations shall be marked on the curb with a "W", "S" and "ST";
- f. A 1" expansion joint shall be provided at 50' intervals, and contraction joints shall be at 5-foot intervals.

- g. Ramping and sloping of sidewalks at intersections shall be in accordance with the specifications and standards as set forth by the Illinois Department of Transportation, the American Disabilities Act (ADA), and the Illinois Disability Code.

Note: All concrete shall be treated with a protective coat application of linseed oil or curing compound equivalent for temperatures over 40 degrees.

SECTION VI

DESIGN REFERENCES

Design References

All work shall be designed and constructed in accordance with the following references as they apply:

1. “Standard Specifications for Road and Bridge Construction,” Illinois Department of Transportation, latest edition.
2. “Manual for Structural Design of Portland Cement Concrete Pavement,” Illinois Department of Transportation, latest edition.
3. “Manual of Instructions for the Structural Design of Flexible Pavements on Projects involving MFT, FAS, and FAUS Funds,” Illinois Department of Transportation, latest edition.
4. “Design Manual,” Illinois Department of Transportation, latest edition.
5. Standard Specifications for Water and Sewer Main Construction in Illinois, latest edition.
6. Kane County “Stormwater Ordinance” as adopted by the City of St. Charles.
7. Transportation Research Board of National Academies “Highway Capacity Manual”, latest edition
8. Federal Highway Administration “Manual on Uniform Traffic Control Devices, for Streets and Highways”, latest edition
9. American Association of State Highway and Transportation Officials “A Policy on Geometric Design of Highways and Streets”, latest edition.

Note: Written requests received prior to final approval for alternate materials and/or construction methods will be reviewed by the Public Works Engineering Division and Community Development Engineering Division prior to final approval.

SECTION VII

INSPECTION PROCEDURES

- A. STORM AND SANITARY**
- B. WATER DISTRIBUTION SYSTEM**
- C. PAVEMENT AND ROADWAYS**

General Note: Inspection of the installation of a development's infrastructure is done to ensure conformance with the Engineering plans and specifications as approved by the City Engineering Divisions. The following sets forth the procedures of the City of St. Charles:

- A. Storm and Sanitary Sewer: Inspection of storm and sanitary sewer improvements throughout St. Charles will be performed to ensure that the project is being constructed in accordance with the approved Final Engineering plans, and to determine if minimum construction and material standards are achieved. If the developer or contractor desires to deviate from the approved plan or does not feel that minimum construction standards are being satisfied, he is responsible for contacting the City immediately. The City of St. Charles will not accept a substandard product, and will not be responsible for any additional cost incurred by the developer / contractor as a result.

Items 1 & 2 of this list of tests shall be required for sanitary sewer improvements in St. Charles. An authorized representative of the City of St. Charles shall supervise all tests. All tests shall be scheduled a minimum of 24 hours in advance.

- 1) Air Test: All sanitary sewers shall pass an air test in conformance with Section 31 of the “Standard Specifications for Water and Sewer Construction in Illinois”. The sewer shall be tested at an initial pressure of 3.5 psig above the level of the ground water, and the time for a pressure drop of 1 psi shall be determined. The time for the pressure drop to occur shall not be less than that specified by the “Standard Specifications for Water and Sewer Construction in Illinois”.
- 2) Deflection Test: All PVC sanitary sewers shall pass a mandrel test in conformance with Section 31 of the “Standard Specifications for Water and Sewer Construction in Illinois”.
- 3) Televising: The Contractor shall provide the Public Works Engineering Division a current color video record and a type written transcription of the internal inspection of the newly constructed sewer system. This shall be submitted prior to refunding of site improvement escrow retention monies by the City of St. Charles and final approval and acceptance of the system. All public and private lines equal to and larger than eight inches in diameter shall be videotaped. The contractor must rotate the lens of the camera to look at all services. The service connections must be noted in the television report. When the proposed sanitary sewer system is to connect to an existing sanitary sewer system abutting the property, the existing sewer must also be televised and reported. The contractor shall coordinate the televising of existing contiguous sewers with the appropriate Engineering Division. Costs associated with this work shall be borne by the contractor.
- 4) Acceptance Inspection: Prior to Council acceptance of public sewers, the City Sewer Division must inspect and approve the improvement. A punchlist of items that require corrective action will be generated, and the developer will coordinate resolution efforts and schedule a re-inspection. Following approval, the acceptance process may proceed. Acceptance inspections will be coordinated through the Development Engineering Office.

5) Maintenance Inspection: Prior to the release of a maintenance guarantee, the City Sewer Division will re-inspect and approve the condition of the sewer improvement. This inspection is performed after a minimum of one year, at the developer's request, or following notification from the financial lending institution that the expiration date for the maintenance letter of credit is approaching. A punchlist of items that require corrective action will be generated, and the developer will coordinate resolution efforts and schedule a re-inspection. Following approval, the maintenance guarantee will be released. The release of the maintenance guarantee shall be coordinated with the Development Engineering Office.

B. Water Distribution System: The mandatory inspection of water main improvements throughout St Charles will be performed to ensure that the project is being constructed in accordance with the approved Final Engineering plans, and to determine if minimum construction and material standards are achieved. If the developer or contractor desires to deviate from the approved plan or does not feel that minimum construction standards are being satisfied, he is responsible for contacting the City immediately. The City of St Charles will not accept a substandard product, and will not be responsible for any additional cost incurred by the developer / contractor as a result.

NOTE: City of St Charles personnel may only operate public water main facilities. The contractor is not permitted to open, close, or adjust any public water valve for any reason. If an emergency situation arises, the contractor shall contact the City of St. Charles Public Works Department immediately.

1) Required Testing: The following is a list of tests, which shall be required for water distribution system improvements in the City of St Charles. . A representative of the City of St Charles Water Division or Public Works Engineering Division shall supervise all tests. All tests shall be scheduled 48 hours in advance.

- a. After a water main has been installed and before the water main has been placed into operation, the contractor shall "bag" or cover fire hydrants. The bag shall not be removed until after the main has become operational. All hydrants shall be placed to face the road.
- b. Flushing: Flushing of all water system improvements will be performed to create a minimum pipeline velocity of 2.5'/per second.
- c. All tests shall be scheduled 48 hours in advance.
- d. Disinfection: All water mains shall pass a disinfection test in conformance with AWWA C65186. The following test criteria shall be met:
 - i. 50-ppm initial chlorine concentration (chlorine gas only)
 - ii. 25-ppm residual chlorine concentration (after 24 hour duration). Sample must be extracted under the supervision of a City of St. Charles representative and analyzed by a laboratory of the Cities choice.
 - iii. Sampling will be performed on two consecutive days, 24 hours apart

- e. Leakage Test: All public water main improvements shall pass a leakage test in conformance with AWWA C-600 and C-603. Allowable leakage in gallons per hour may not exceed that determined by the following formula:

$$L = \frac{ND\sqrt{P}}{7400}$$

L = Allowable leakage in gallons per hour

N = Number of joints in length of tested main

D = Nominal inside diameter of pipe in inches

P = Average test pressure in psi

- f. Pressure Test:

All public water main improvements shall pass a pressure test in conformance with the requirements of ANSI/AWWA C600-87 Section 4, and the Testing requirements shall follow the “Standard Specifications for Water and Sewer Main Construction in Illinois”, latest edition..

The contractor shall, after installation of the water main system or parts thereof, pressure test and chlorinate the new system. A two-hour pre-test must be made and passed by the Contractor before scheduling the pressure test with the City. The main shall then be pressure tested at 150 PSI for a duration of two hours in the presence of a representative of the City Engineering Division. If a scheduled pressure test does not pass because of the failure of the Contractor to hold a pre-test, the City may charge a reinspection fee to the Contractor. Any other water main work will be halted until the reinspection fees have been paid.

After a successful pressure test, the main shall be chlorinated by gas injection method only, by a qualified technician. Samples shall be taken on 2 consecutive working days, Monday through Friday, 24 hours after chlorination, and after the main has been flushed. A City representative shall determine the number of samples taken. A City representative must be present for the pressure testing, chlorination, flushing, and drawing of the sample. The contractor shall bear the costs of these tests and reinspection fees. If after four samplings, the results do not yield two consecutive satisfactory readings, a re-chlorination will be necessary.

Only the City of St Charles Water Division shall make the water system operational after receiving satisfactory lab reports from a qualified testing lab.

- g. All private fire service lines shall pass a pressure test in conformance with the requirements of ANSI/AWWA C600-87 Section 4. The following test criteria shall be met:

- i. 200 psi minimum initial test pressure
- ii. 200 psi minimum residual pressure after two hours
- iii. If an existing valve is utilized for the pressure test, the contractor is responsible for the performance of the valve
- iv. Test to be observed by City of St. Charles Fire Department representative
- v. If the pressure gauge fails to ‘zero’ at the end of the test, the test will be failed

2) Inspections:

- a. Notice: The developer or contractor shall contact the City of St. Charles Water Division a minimum of 48 hours in advance of a scheduled inspection.
- b. Acceptance Inspection: Prior to Council acceptance of a public watermain, the City Water Division must inspect and approve the improvement. A punchlist of items, which require corrective action, will be generated, and the developer will coordinate resolution efforts and schedule a re-inspection. Following approval, the acceptance process may proceed. Acceptance proceedings will be coordinated through the Engineering Office
- c. Maintenance Inspection: Prior to the release of a maintenance guarantee, the City Water Division must inspect and approve the condition of the water main. This inspection is performed just prior to one year from the date of City council acceptance of the improvements. This will be at the developer's request, or following notification from the financial lending institution that the expiration date for the maintenance letter of credit is approaching. A punchlist of items, which require corrective action, will be generated, and the developer will coordinate resolution efforts and schedule a re-inspection. Following approval, the maintenance guarantee will be released. The release of the maintenance guarantee shall be coordinated with the Public Works Engineering Office.
- d. B-Boxes: Upon completion of the project, the B-boxes will be adjusted to grade, and checked to see if they are operational without altering the shutoff key. Locations of the B-box with measurements to the property lines shall be supplied to the Public Works Engineering Division and shown on the as-built plans for the project. The Water Division for locating B-boxes will issue a charge. B-box locations shall be marked on the curb/sidewalk with a "W".

C. Pavement and Roadways: Inspection of roadway and paving projects throughout St. Charles will be performed to ensure that traffic control is in place and functional, that the project is being constructed in accordance with the approved Final Engineering plans, and to determine if minimum construction and material standards are achieved. If the developer or contractor desires to deviate from the approved plan or does not feel that minimum construction standards are being satisfied, the Contractor is responsible for contacting the City immediately. The City of St. Charles will not accept a substandard product, and will not be responsible for any additional cost incurred by the developer / contractor as a result.

1) Inspections:


- a. Notice: The developer or contractor shall contact the City of St Charles appropriate Engineering Division a minimum of 24 hours in advance of a scheduled inspection.

- b. Acceptance Inspection: Prior to Council acceptance of a public roadway, the City Engineering Office must inspect and approve the improvement. A punchlist of items, which require corrective action, will be generated, and the developer will coordinate resolution efforts and schedule a re-inspection. Following Engineering approval, the acceptance process may proceed. New pavement will be tested by a City appointed consultant to ensure that the structural strength of said pavement will provide a minimum of twenty (20) years of service life after acceptance. The cost for said testing shall be borne by the developer. This testing shall be completed and approved the City immediately prior to placement of the final surface course of asphalt.
- c. Curb Inspection: An inspection is required for all curb work in the public R.O.W.. The contractor shall contact the Engineering Office 24 hours in advance of the scheduled pour. An Engineering Office representative must inspect and approve the base, forms, alignment, and location, and expansion material prior to the pour.
- d. Maintenance Inspection: Prior to the release of a maintenance guarantee, the City Engineering Office will re-inspect and approve the condition of the roadway. This inspection is performed after a minimum of one year, at the developer's request, or following notification from the financial lending institution that the expiration date for the maintenance letter of credit is approaching. A punchlist of items, which require corrective action, will be generated, and the developer will coordinate resolution efforts and schedule a re-inspection. Following Engineering approval, the maintenance guarantee will be released.
- e. Sidewalk Inspection: An inspection is required for all public sidewalks. The contractor shall contact the Engineering Office 24 hours in advance of the scheduled pour. An Engineering Office representative must inspect and approve the sidewalk base, forms, alignment, and expansion material prior to the pour.
- f. Compaction Test: Compaction tests of the sub-base, base, and surface courses of the pavement shall be made by a qualified testing lab, and must be made in the presence of a representative of the City of St. Charles Engineering Department. The developer/contractor shall bear the cost of the testing. The shape and thickness of the pavement base and sub-base must be checked and approved by a representative of the City Engineering Division before the placement of the next course. Prior to the placement of the surface course, a preliminary punch list generated by the Public Works and Engineering Division must be completed by the contractor.

SECTION VIII

ENGINEERING DETAILS

BRICK PAVING DETAIL



NOTES


1. PLACEMENT OF PAVER BRICKS OR STAMPED CONCRETE REQUIRE A NON STANDARD PAVEMENT, NOTORIZED PERMIT AGREEMENT AND A "COVENANT RUNNING WITH THE LAND" DOCUMENT, WHICH MUST BE RECORDED AT KANE COUNTY RECORDERS OFFICE PRIOR TO CONSTRUCTION.
2. THE SAND FOR THE BEDDING LAYER SHALL BE DELIVERED TO THE SITE A MINIMUM OF 24 HOURS PRIOR TO PLACEMENT TO ALLOW FOR THE MOISTURE TO DRAIN FROM THE MATERIAL.
3. THE SAND BED SHALL BE COMPACTED PRIOR TO PLACEMENT OF THE PAVER BRICKS. DISTURBED AREAS OR SCREEDED AREAS LEFT OVERNIGHT SHALL BE REMOVED AND RESCREEDED. FOLLOWING THE PLACEMENT OF THE PAVER BRICKS, FA-1 SAND SHALL BE SPREAD ACROSS THE SURFACE OF THE SURFACE OF THE PAVERS AND COMPACTED WITH A VIBRATORY PLATE COMPACTOR.
4. THE BASE COURSE SHALL BE CONSTRUCTED OF CA-6 MATERIAL COMPACTED IN TWO LIFTS.
5. EDGE RESTRAINT SHALL BE PROVIDED ON ALL SIDES OF THE PAVER CONSTRUCTION IN THE FORM OF STANDARD CURB AND GUTTER, SIDEWALK, OR THE TYPICAL EDGE RESTRAINT SHOWN ABOVE
6. UNDERCUTS AND THE CONSTRUCTION OF A SUBBASE SHALL OCCUR AS NECESSARY TO ENSURE THE STRUCTURAL STABILITY OF THE ROADWAY.

NOT TO SCALE

BRICK
PAVING
DETAIL

DATE: 3-31-09

BRICK PAVING DETAIL




NOTES

1. PLACEMENT OF P.C.C. AND PAVING BRICKS SHALL BE DONE IN PHASES TO ENSURE THAT STREET IS OPEN TO TRAFFIC AT ALL TIMES UNLESS STREET CLOSURE IS PERMITTED BY ENGINEER.
2. P.C.C. SHALL CONSIST OF IDOT CLASS SI (6.1 BAG MIX) CONCRETE, WITH 5% TO 8% AIR ENTRAINMENT, AND A MINIMUM COMPRESSIVE STRENGTH OF 3,500 PSI AT 14 DAYS.(NO FLY ASH ALLOWED)
3. REFER TO IDOT STANDARD 442101-07 (CLASS B PATCHES) FOR DOWEL BAR AND JOINT DETAILS FOR P.C.C. BASE.

NOT TO SCALE

BRICK PAVING
IN ROADWAY

DATE: 1-18-12





NOTES:

1. VALVE VAULT MUST CONFORM TO ASTM C-478.
2. USE ECCENTRIC CONE ONLY.
3. VAULT SECTIONS TO BE TONGUE AND GROOVED.
4. ALL NON-PRECAST PIPE OPENINGS TO BE CORED AND RUBBER BOOTED.
5. BACKFILL MATERIAL SHALL BE IDOT CA-7 VIRGIN CRUSHED LIMESTONE.
6. ALL BOLTS, NUTS & WASHERS SHALL BE 304 GRADE STAINLESS STEEL.
7. PRIOR TO THE PLACEMENT OF FINAL LAYER OF ROADWAY, FRAMES AND ADJUSTING RINGS LOCATED WITHIN PAVED AREAS SHALL BE SET IN AN IDOT APPROVED CONCRETE "SI" MIXTURE.

DATE: 7-27-10

NOT TO SCALE

**BUTTERFLY
VALVE
VAULT
DETAIL**



MIN $\frac{3}{8}$ " THICK BITUMINOUS COATED STEEL CASING PIPE, AUGERED & JACKED

INSTALL ALL STAINLESS STEEL CASING SPACERS (BY CASCADE OR APPROVED EQUAL) FOR EACH PIPE LENGTH ON 6' CENTERS, OR AS RECOMMENDED BY THE MANUFACTURER

SANITARY SEWER, STORM SEWER OR WATER MAIN (CARRIER PIPE)

BRICK AND MORTAR BULKHEAD (BOTH ENDS) AS APPROVED BY THE CITY ENGINEERING DIVISION, PRIOR TO BACKFILLING OR INSTALL END BOLTS (BY CASCADE OR APPROVED EQUAL)


NOTES:

1. CASING PIPE IS REQUIRED UNDER ALL EXISTING ROADWAYS, OR AS OTHERWISE DIRECTED BY THE ENGINEERING DIVISION WHERE OPEN CUTS ARE NOT PERMITTED, EXCEPT FOR WATER SERVICE LINES UP TO 2" IN DIAMETER.
2. WATER MAIN CASING SPACERS SHALL BE RESTRAINED IN POSITION.
3. THE INSIDE DIAMETER OF THE CASING PIPE SHALL BE DETERMINED BY CONTRACTOR BUT IN NO CASE SHALL IT BE LESS THAN 8" LARGER THAN THE DIAMETER OF THE CARRIER PIPE TO ALLOW AMPLE SPACE FOR BELLS, AND CARRIER PIPE SLOPE (FOR GRAVITY PIPE).
4. ALL AUGER PITS TO BE BACKFILLED WITH IDOT CA-7 VIRGIN CRUSHED LIMESTONE MATERIAL.
5. POLY WRAPPED WATER MAIN REQUIRED IN CASING.

NOT TO SCALE

CASING PIPE
DETAIL

DATE: 11-2-09




NOTES:

1. MANHOLES MUST CONFORM TO ASTM C-478.
2. MANHOLE SECTIONS TO BE TONGUE AND GROOVED.
3. NON-PRECAST OPENINGS SHALL BE CORED AND RUBBER BOOTED.
4. MORTAR ALL PENETRATIONS INSIDE AND OUTSIDE OF STRUCTURE.
5. IN "SUBMERGED" CONDITIONS, ALL PIPE PENETRATIONS TO BE CORED, RUBBER BOOTED AND INTERIOR MORTARED.
6. PRIOR TO THE PLACEMENT OF FINAL LAYER OF ROADWAY, FRAMES AND ADJUSTING RINGS LOCATED WITHIN PAVED AREAS SHALL BE SET IN AN IDOT APPROVED CONCRETE "SI" MIXTURE.

NOT TO SCALE

**TYPE A & B
CATCH BASIN
DETAIL**

DATE: 7-27-10




NOTE:

1. CATCH BASIN TO BE CONSTRUCTED OF PRECAST REINFORCED CONCRETE.
2. CATCH BASIN MUST CONFORM TO ASTM C-478.
3. NON-PRECAST OPENINGS SHALL BE CORED AND RUBBER BOOTED.
4. MAXIMUM DEPTH FROM INVERT OF OUTLET PIPE TO TOP OF FRAME SHALL NOT EXCEED 42 INCHES. IF DESIGN OR CONSTRUCTION REQUIRES DEPTH BEYOND 42 INCHES, STRUCTURE SHALL BE REVISED TO A 48 INCH DIAMETER TYPE C CATCH BASIN.

NOT TO SCALE

**TYPE C
CATCH BASIN
DETAIL**

DATE: 8-18-10



**INTERNAL CHIMNEY SEALS
TO SPAN CHIMNEY HEIGHTS OF:**

- 0 - 4½" CHIMNEY SEAL ONLY
- 4½" TO 9" SEAL + 7" EXTENSION
- 9" TO 12" SEAL + 10" EXTENSION
- OVER 12" SEAL + MULTI. EXTENSIONS

**EXTERNAL CHIMNEY SEALS
TO SPAN CHIMNEY HEIGHTS OF:**

- 0 - 3" NARROW (6") SEAL ONLY
- 3 TO 6½" STANDARD (9") SEAL ONLY
- 6½" TO 12" STD. SEAL + EXTENSION
- OVER 12" SEAL + MULTI. EXTENSIONS

NOTE:

1. CHIMNEY SEALS SHALL BE INSTALLED ON ALL SANITARY SEWER SYSTEM MANHOLES.
2. "CRETEX" OR APPROVED EQUAL EXTERNAL/INTERNAL SEALS ARE REQUIRED. OTHER PRODUCTS OR OTHER DESIGN SOLUTIONS SHALL REQUIRE THE APPROVAL OF THE CITY ENGINEERING DEPARTMENT.
3. IF INTERNAL SEALS ARE USED, THE STRUCTURE, INCLUDING ADJUSTMENT RINGS, MUST BE INSPECTED BY CITY PERSONNEL BEFORE INSTALLATION.
4. CHIMNEY SEALS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS.


NOT TO SCALE

**CHIMNEY
SEAL
DETAIL**

DATE: 3-31-09

CONTRACTION JOINT DETAIL

EXPANSION JOINT DETAIL




NOTES:

1. UNLESS OTHERWISE NOTED ON PLANS,
CONTRACTION JOINTS TO BE AT 5'-0" O.C.
2. EXPANSION JOINTS TO BE 50'-0" O.C. MAX.
OR AT BACK OF CURB, CHANGE OF DIRECTION,
OTHER WALK, UTILITY APPURTENANCE, OR
FACE OF STRUCTURE.
3. PORTLAND CEMENT CONCRETE SHALL CONFORM TO
IDOT CLASS SI, MIN. 3.500 PSI (6.1 BAG MIX)
AT 14 DAYS, WITH 5% TO 8% AIR ENTRAINMENT.
(NO FLY ASH ALLOWED)


NOT TO SCALE

CONCRETE WALK
JOINT DETAILS


DATE: 3-31-09



PLAN



ELEVATION



SECTION A-A


NOTES:

1. GEOTEXTILE FILTER FABRIC SHALL BE PLACED OVER THE CLEARED AREA PRIOR TO PLACING COARSE AGGREGATE
2. COARSE AGGREGATE (OR CRUSHED CONCRETE) SHALL MEET IDOT GRADATION FOR CA-1 CRUSHED AGGREGATE.
3. STABILIZED CONSTRUCTION ENTRANCE SHALL BE INSTALLED, PRIOR TO ONSET OF CONSTRUCTION OPERATIONS AND SHALL BE MAINTAINED THROUGHOUT THE PROJECT.
4. CONSTRUCTION ENTRANCE SHALL BE REMOVED UPON COMPLETION OF CONSTRUCTION AND ONLY WHEN DIRECTED BY THE CITY.

NOT TO SCALE

STABILIZED
CONSTRUCTION
ENTRANCE
DETAIL

DATE: 3-31-09



NOTES:


- 1.) ISLANDS ARE OPTIONAL AT THE DISCRETION OF THE CITY.
- 2.) FIRE HYDRANTS AND STREET LIGHTS SHALL BE LOCATED IN THE THROAT OF THE CUL-DE-SAC AND NOT THE BULB UNLESS DIRECTED BY THE CITY
- 3.) REFER TO TABLE 1 ON PAGE 27 OF THE ENGINEERING DESIGN AND INSPECTION POLICY MANUAL FOR MINIMUM REQUIRED PAVEMENT WIDTHS.

NOT TO SCALE


ECCENTRIC
CUL-DE-SAC

DATE: 4-2-13

DEPRESSED CURB



B4.12 CURB & GUTTER



NOTES:


1. CONTRACTION JOINTS SHALL BE PLACED AT 15' INTERVALS, AND SHALL BE GROOVED WITH AN EDGING TOOL. SEE ARTICLE 420.10 OF IDOT STANDARD SPECIFICATIONS.
2. EXPANSION JOINTS SHALL BE PLACED AT 60' (MAX) INTERVALS, AT ALL P.C.'S AND P.T.'S, CURB RETURNS, AND AT THE END OF EACH POUR
3. P.C.C. SHALL CONSIST OF IDOT CLASS SI (6.1 BAG MIX) CONCRETE, WITH 5% TO 8% AIR ENTRAINMENT, AND A MINIMUM COMPRESSIVE STRENGTH OF 3,500 PSI AT 14 DAYS. (NO FLY ASH ALLOWED)

FOR RESIDENTIAL STREETS ONLY


DATE: 10-22-10
NOT TO SCALE

B4.12 COMB. CONCRETE CURB AND GUTTER (SPECIAL)
B4.12 P.C.C. INTEGRAL CURB AND GUTTER (SPECIAL)

DEPRESSED CURB



B6.12 CURB & GUTTER



NOTES:


1. CONTRACTION JOINTS SHALL BE PLACED AT 15' INTERVALS, AND SHALL BE GROOVED WITH AN EDGING TOOL. SEE ARTICLE 420.10 OF IDOT STANDARD SPECIFICATIONS.
2. EXPANSION JOINTS SHALL BE PLACED AT 60' (MAX) INTERVALS, AT ALL P.C.'S AND P.T.'S, CURB RETURNS, AND AT THE END OF EACH POUR
3. P.C.C. SHALL CONSIST OF IDOT CLASS SI (6.1 BAG MIX) CONCRETE, WITH 5% TO 8% AIR ENTRAINMENT, AND A MINIMUM COMPRESSIVE STRENGTH OF 3,500 PSI AT 14 DAYS. (NO FLY ASH ALLOWED)

FOR RESIDENTIAL STREETS ONLY


DATE: 10-22-10
NOT TO SCALE

B6.12 COMB. CONCRETE CURB AND GUTTER (SPECIAL)
B6.12 P.C.C. INTEGRAL CURB AND GUTTER (SPECIAL)

DEPRESSED CURB



B6.18 CURB & GUTTER




NOTES:

1. CONTRACTION JOINTS SHALL BE PLACED AT 15' INTERVALS, AND SHALL BE GROOVED WITH AN EDGING TOOL. SEE ARTICLE 420.10 OF IDOT STANDARD SPECIFICATIONS.
2. EXPANSION JOINTS SHALL BE PLACED AT 60' (MAX) INTERVALS, AT ALL P.C.'S AND P.T.'S, CURB RETURNS, AND AT THE END OF EACH POUR
3. P.C.C. SHALL CONSIST OF IDOT CLASS SI (6.1 BAG MIX) CONCRETE, WITH 5% TO 8% AIR ENTRAINMENT, AND A MINIMUM COMPRESSIVE STRENGTH OF 3,500 PSI AT 14 DAYS. (NO FLY ASH ALLOWED)

FOR RESIDENTIAL STREETS ONLY

DATE: 10-22-10
NOT TO SCALE

B6.18 COMB. CONCRETE CURB AND GUTTER (SPECIAL)
B6.18 P.C.C. INTEGRAL CURB AND GUTTER (SPECIAL)



NOTES:


1. CURB INLET CASTING SHALL BE FASTENED TEMPORARILY TO FRAME CASTING WITH 2 CAP SCREWS, DURING CONSTRUCTION
2. CAP SCREWS MUST BE REMOVED AFTER CURB HAS HARDENED.

PROFILE VIEW

NOTE:

COST OF ADDITIONAL GUTTER TO MATCH DETAIL INCIDENTAL

TOP OF CURB TO TRANSITION FROM 6" HIGH TO 3" HIGH



NOTES:


1. CURB CONTRACTOR TO VERIFY POSITION AND ELEVATION OF FRAME AND GRATE PRIOR TO POUR. IF NOT CORRECT, FIVE (5) FOOT TRANSITION AREA TO BE LEFT UNPOURED UNTIL SITUATION IS CORRECTED BY CONTRACTOR.

PLAN VIEW

NOT TO SCALE

**B-6.18
CURB AND
GUTTER
FOR R-3250
CURB INLET**

DATE: 3-31-09




NOTES:

1. FOR P.C.C. DRIVEWAY OVER AN UNDERGROUND UTILITY TRENCH, PLACE 6X6 - W2.9XW2.9 WELD AND WIRE FABRIC AT MID-DEPTH OF THE CONCRETE.
2. FOR CONCRETE APPROACH WIDER THAN 16', A CONTRACTION JOINT SHALL BE LOCATED ALONG THE CENTERLINE.
3. P.C.C. CONCRETE DRIVEWAYS:
 APPROACH- 6" (MIN) PORTLAND CEMENT CONCRETE AND 4" (MIN) IDOT CA-6 CRUSHED STONE
 DRIVEWAY- 5" (MIN) PORTLAND CEMENT CONCRETE AND 4" (MIN) IDOT CA-6 CRUSHED STONE
4. BITUMINOUS DRIVEWAYS:
 APPROACH- 6" (MIN) IDOT CA-6 CRUSHED STONE AND 3" (MIN) BITUMINOUS CONCRETE
 DRIVEWAY- 4" (MIN) IDOT CA-6 CRUSHED STONE AND 3" (MIN) BITUMINOUS CONCRETE
5. BRICK PAVERS OR OTHER ARCHITECTURAL PAVING MATERIALS ARE NOT ALLOWED IN A DRIVEWAY APPROACH AREA WITHOUT A BUILDING PERMIT AND WRITTEN PERMISSION -INCLUDING A HOLD HARMLESS AGREEMENT- FROM THE ENGINEERING DIVISION
6. MAINTAIN FULL SIDEWALK WIDTH THROUGH DRIVEWAYS UNLESS DIRECTED OTHERWISE BY CITY ENGINEER. CURBING SHALL NOT RUN THROUGH SIDEWALK AREAS IN DRIVEWAYS.

NOT TO SCALE

**DRIVEWAY
DETAIL**

DATE: 3-31-09





NOTE:

1. DROP MANHOLE WILL BE REQUIRED WHERE DIFFERENCE BETWEEN INVERT ELEVATION OF INLET AND DOWNSTREAM PIPE IS GREATER THAN 12".
2. NON-PRECAST OPENINGS SHALL BE CORED AND RUBBER BOOTED.

DATE: 3-31-09

NOT TO SCALE

**DROP MANHOLE
DETAIL**







GENERAL NOTES:


FRAME: Top flange fabricated from 1¼"x1¼"x½" angle. Base rim fabricated from 1½"x½"x½" channel. Handles and suspension brackets fabricated from 1¼"x¼" flat stock. All steel conforming to ASTM-A36.

SEDIMENT BAG: Bag fabricated from 4 oz./sq.yd. non-woven polypropylene geotextile reinforced with polyester mesh. Bag secured to base rim with a stainless steel band and lock.

DATE	REVISIONS	Typical Beehive Catch-All
01-22-02	Original	
		Marathon Materials, Inc.



Fabric Flap to cover curb box



GENERAL NOTES:






FRAME: Top flange fabricated from 1 1/4"x1 1/4"x1/8" angle. Base rim fabricated from 1 1/2"x1/2"x1/8" channel. Handles and suspension brackets fabricated from 1 1/4"x1/4" flat stock. All steel conforming to ASTM-A36.

SEDIMENT BAG: Bag fabricated from 4 oz./sq.yd. non-woven polypropylene geotextile reinforced with polyester mesh. Bag secured to base rim with a stainless steel band and lock.

DATE	REVISIONS
01-11-02	Original
05-07-04	Remove Back Rail

Typical Curb Box
Catch-All

Marathon Materials, Inc.



GENERAL NOTES:





FRAME: Top flange fabricated from $1\frac{1}{4}'' \times 1\frac{1}{4}'' \times \frac{1}{8}''$ angle. Base rim fabricated from $1\frac{1}{2}'' \times \frac{1}{2}'' \times \frac{1}{8}''$ channel. Handles and suspension brackets fabricated from $1\frac{1}{4}'' \times \frac{1}{4}''$ flat stock. All steel conforming to ASTM-A36.

SEDIMENT BAG: Bag fabricated from 4 oz./sq.yd. non-woven polypropylene geotextile reinforced with polyester mesh. Bag secured to base rim with a stainless steel band and lock.

DATE	REVISIONS
01-22-02	Original

Typical Rectangular
Catch-All

Marathon Materials, Inc.




GENERAL NOTES:

FRAME: Top flange fabricated from 1 1/4" x 1 1/4" x 1/8" angle. Base rim fabricated from 1 1/2" x 1/2" x 1/8" channel. Handles and suspension brackets fabricated from 1 1/4" x 1/4" flat stock. All steel conforming to ASTM-A36.

SEDIMENT BAG: Bag fabricated from 4 oz./sq.yd. non-woven polypropylene geotextile reinforced with polyester mesh. Bag secured to base rim with a stainless steel band and lock.

DATE	REVISIONS	Typical Round Catch-All
01-11-02	Original	
		Marathon Materials, Inc.

CULVERT INLET PROTECTION - SILT FENCE



PLAN VIEW

NOTES:


1. The silt fence shall meet the requirements as shown on standard drawing IL-620 SILT FENCE except the maximum post spacing shall be 3 feet and the tops of posts shall be cross braced.
2. Sediment shall be removed when the sediment has accumulated to one-half the height of the silt fence.
3. The maximum drainage area to the culvert being protected is 1 acre.

REFERENCE			
Project	_____		
Designed	_____	Date	_____
Checked	_____	Date	_____
Approved	_____	Date	_____



STANDARD DWG. NO.
 IL-508SF
 SHEET 1 OF 1
 DATE 1-29-99

CULVERT INLET PROTECTION - STONE




Notes:


1. Sediment shall be removed when the sediment has accumulated to one-half the height of the stone berm.
2. Coarse aggregate shall meet one of the following IDOT coarse aggregate gradations, CA-1, CA-2, CA-3 or CA-4.
3. Riprap shall meet IDOT gradation RR-3 or RR-4. Any permanent riprap, such as for the culvert headwall, shall meet IDOT Quality Designation A.
4. Coarse aggregate and riprap shall be placed according to construction specification 25 ROCKFILL using placement Method 1 and Class III compaction.
5. The maximum drainage area to the culvert being protected is 3 acres.
6. See plans for H dimension.
7. Tie the stone berm into the culvert embankment a minimum of 1 foot above the design elevation of the stone berm.

<p>REFERENCE</p> <p>Project _____</p> <p>Designed _____ Date _____</p> <p>Checked _____ Date _____</p> <p>Approved _____ Date _____</p>	 <p>NRCS</p> <p>Natural Resources Conservation Service</p>	<p>STANDARD DWG. NO.</p> <p>IL-508ST</p> <p>SHEET 1 OF 1</p> <p>DATE 1-29-99</p>
-----------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------

INLET PROTECTION - EXCAVATED DRAIN PLAN



PLAN VIEW



TYPICAL SECTION A-A

NOTES:


1. Sediment shall be removed and the trap restored to its original dimensions when the sediment has accumulated to 1/2 the design depth of the trap. Removed sediment shall be deposited in a suitable area and in such a manner that it will not erode.
2. The sediment trap shall be removed and the area stabilized when the constructed drainage area has been properly stabilized.
3. All cut slopes shall be 2:1 or flatter.

REFERENCE	
Project	_____
Designed	_____ Date _____
Checked	_____ Date _____
Approved	_____ Date _____



STANDARD DWG. NO.
IL-555
SHEET 1 OF 1
DATE 3-11-93

INLET PROTECTION - FABRIC DROP PLAN



NOTES:

1. Filter fabric shall meet the requirement of material specification 592 GEOTEXTILE table 1 or 2, class I, with an EDS of at least 30 for nonwoven and 50 for woven.
2. The wire mesh shall have a maximum opening of at least 6 inches.
3. Limit drainage area to the inlet protection to 1 acre.

REFERENCE	
Project	_____
Designed	_____ Date _____
Checked	_____ Date _____
Approved	_____ Date _____




NRCS


Natural Resources Conservation Service

STANDARD DWG. NO.
IL-560
SHEET 1 OF 1
DATE 6-29-93

INLET PROTECTION SOD FILTER PLAN



PLAN



SECTION

NOTES:



1. The sod should be flush with surrounding ground surface.
2. If used, filter fabric shall meet the requirements of material specification 592 GEOTEXTILE Table 1 or 2, Class 1 with AOS of at least 30 for nonwoven and 50 for woven.

REFERENCE	
Project	_____
Designed	_____ Date _____
Checked	_____ Date _____
Approved	_____ Date _____



STANDARD DWG. NO.	IL-562
SHEET	1 OF 1
DATE	11-23-01

ROCK CHECK DAM - COARSE AGGREGATE



NOTES:


1. Filter fabric shall meet the requirements of material specification 592 GEOTEXTILE, Table 1 or 2, Class I, II, or IV and shall be placed over the cleared area prior to the placing of rock.
2. Coarse aggregate shall meet one of the following IDOT gradations, CA-1, CA-2, CA-3, or CA-4 and be placed according to construction specification 25 ROCKFILL using placement Method 1 and Class III compaction.
3. For added stability, the base of the dam may be keyed 6 inches into the soil.
4. See plans for spacing of dams and H dimensions.
5. Drainage area to each dam shall be less than 2 acres.
6. Use ROCK CHECK DAM-RIPRAP IL-605R for drainage areas of 2 to 10 acres.

REFERENCE	
Project	_____
Designed	_____ Date _____
Checked	_____ Date _____
Approved	_____ Date _____




STANDARD DWG. NO.
 IL-605CA
 SHEET 1 OF 1
 DATE 1-29-99

ROCK CHECK DAM - RIPRAP



PROFILE



CROSS SECTION

CENTERLINE LOOKING DOWNSTREAM

NOTES;

1. Filter fabric shall meet the requirements of material specification 592 GEOTEXTILE, Table 1 or 2, Class I, II, or IV and shall be placed over the cleared area prior to the placing of rock.
2. Coarse aggregate shall meet one of the following IDOT gradations, CA-1, CA-2, CA-3, or CA-4.
3. Riprap shall meet IDOT gradation RR-3 or RR-4 and meet Quality Designation A.
4. Coarse aggregate and riprap shall be placed according to construction specification 25 ROCKFILL using placement Method 1 and Class III compaction.
5. For added stability, the base of the dam may be keyed 6 inches into the soil.
6. See plans for spacing of dams and H dimensions.
7. Maximum drainage area to each dam is 10 acres.
8. ROCK CHECK DAM-COARSE AGGREGATE IL-605CA may be used for drainage areas under 2 acres.

REFERENCE

Project _____
 Designed _____ Date _____
 Checked _____ Date _____
 Approved _____ Date _____






NRCS

Natural Resources Conservation Service

STANDARD DWG. NO.

IL-605R
 SHEET 1 OF 1
 DATE 1-29-99

PLASTIC PERMEABLE CHECKS



REFERENCE

Project _____
 Designed _____ Date _____
 Checked _____ Date _____
 Approved _____ Date _____



STANDARD DWG. NO.


IUM-514

SHEET 1 OF 1

DATE 8-19-11

ROLLED EROSION CONTROL PRODUCTS


Staking Pattern Guide




Notes:

1. Overlap minimum is the diameter of the roll.
2. 4' spacing for wattles.
3. 2' spacing for rolled excelsior.
4. Or space according to manufacturer's specifications.

Stake Detail



Compost Filter Sock Detail



When compost filter sock ditch check is used, place a compost berm upstream of the filter sock (see IUM 805). A trench is not required.

Notes:

1. Drawings are not to scale.
2. Ends of wattles or rolled excelsior shall be turned at least 6" upslope.
3. Recommended stakes are 1 1/8" wide x 1 1/8" thick x 30" long
4. Stakes shall not extend above the straw wattle more than 2".
5. Spacing: The toe of the upstream ditch check shall create a horizontal line with the top of the downstream ditch check.
6. When compost filter sock ditch check is used, place a compost berm upstream of the filter sock (see IUM 805). A trench is not required.

REFERENCE

Project _____
 Designed _____ Date _____
 Checked _____ Date _____
 Approved _____ Date _____






STANDARD DWG. NO.

IUM-514


SHEET 1 OF 1

DATE 8-19-11

SYNTHETIC POROUS RUNOFF CONTROL STRUCTURES



Minimum Installation Length up Slopes	
Slope	Panels
2:1	1
2.5:1	1.5
3:1	2
3.5:1	2
4:1	2
5:1	2.5
6:1	2.5



REFERENCE

Project _____

Designed _____ Date _____



Checked _____ Date _____

Approved _____ Date _____





STANDARD DWG. NO.
IUM-514
SHEET 1 OF 1
DATE 8-19-11

URETHANE FOAM GEOTEXTILES



<p>REFERENCE</p> <p>Project _____</p> <p>Designed _____ Date _____</p> <p>Checked _____ Date _____</p> <p>Approved _____ Date _____</p>	 <p>ILLINOIS URBAN MANUAL</p>	<p>STANDARD DWG. NO.</p> <p>IUM-514</p> <p>SHEET 1 OF 1</p> <p>DATE 6-30-11</p>
-----------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------



VEGETATED DITCH CHECK




REFERENCE	
Project	_____
Designed	_____
Checked	_____
Approved	_____
Date	_____
Date	_____
Date	_____




STANDARD DWG. NO.
IUM-514
SHEET 1 OF 1
DATE 6-30-11




DETAIL 1




DETAIL 2



DETAIL 3



STAPLE DETAIL





PUSH PIN DETAIL


NOTES:

1. Staples shall be placed in a diamond pattern at 2 per s.y. for stiched blankets. Non-stiched shall use 4 staples per s.y. of material. This equates to 200 staples with stiched blanket and 400 stapels with non-stiched blanket per 100 s.y. of material.
2. Staple or push pin lengths shall be selected based on soil type and conditions. (minimum staple length is 6")
3. Erosion control material shall be placed in contact with the soil over a prepared seedbed.
4. All anchor slots shall be stapled at approximately 12" intervals.


EROSION CONTROL BLANKET - TURF REINFORCEMENT MAT (TRM)





DETAIL 1



DETAIL 2



DETAIL 3



***Note:**


1. For sandy soil conditions, staple or push pin shall be a minimum 8 inches.

REFERENCE	
Project	_____
Designed	_____ Date _____
Checked	_____ Date _____
Approved	_____ Date _____



STANDARD DWG. NO.
IUM-531
SHEET 1 OF 1
DATE 02-22-11

INLET PROTECTION - PAVED AREAS CURB PROTECTION



REFERENCE

Project	_____
Designed	_____ Date _____
Checked	_____ Date _____
Approved	_____ Date _____





STANDARD DWG. NO.

IUM-561C

SHEET 1 OF 1

DATE 01-11-11

INLET PROTECTION - PAVED AREAS DROP-IN PROTECTION





REFERENCE
 Project _____
 Designed _____ Date _____
 Checked _____ Date _____
 Approved _____ Date _____



STANDARD DWG. NO.
IUM-561D
 SHEET 1 OF 1
 DATE 01-11-11

SILT FENCE PLAN



NOTES:

1. Temporary sediment fence shall be installed prior to any grading work in the area to be protected. They shall be maintained throughout the construction period and removed in conjunction with the final grading and site stabilization.
2. Filter fabric shall meet the requirements of material specification 592 Geotextile Table 1 or 2, Class I with equivalent opening size of at least 30 for nonwoven and 40 for woven.
3. Fence posts shall be either standard steel post or wood post with a minimum cross-sectional area of 3.0 sq. in.

REFERENCE

Project _____
 Designed _____ Date _____
 Checked _____ Date _____
 Approved _____ Date _____




STANDARD DWG. NO.

IUM-620A


SHEET 1 OF 2

DATE 3-16-12

SILT FENCE WITH WIRE SUPPORT PLAN



ELEVATION



FABRIC ANCHOR DETAIL

STATIC SLICE INSTALLATION

TRENCH INSTALLATION

NOTES:


1. Silt Fence shall be installed prior to any grading work in the area to be protected. They shall be maintained throughout the construction period and removed in conjunction with the final grading and site stabilization. Silt fence shall be placed on the flattest area available.
2. Filter fabric shall meet the requirements of material specification 592 Geotextile Table 1 or 2, Class I with equivalent opening size of at least 30 for nonwoven and 40 for woven.
3. Fence posts shall be either standard steel post or wood post with a minimum cross-sectional area of 3.0 sq. in.

REFERENCE	
Project	_____
Designed	_____ Date _____
Checked	_____ Date _____
Approved	_____ Date _____



STANDARD DWG. NO.
IUM-620A(W)
SHEET 1 OF 2
DATE 3-16-2012

SILT FENCE - SPLICING TWO FENCES



ATTACHING TWO SILT FENCES

1. Place the end post of the second fence inside the end post of the first fence.
2. Rotate both posts at least 180 degrees in a clockwise direction to create a tight seal with the fabric material.
3. Cut the fabric near the bottom of the stakes to accommodate the 6" flap.
4. Drive both posts a minimum of 18 inches into the ground and bury the flap.
5. Compact backfill (particularly at splices) completely to prevent stormwater piping.

REFERENCE

Project _____
 Designed _____ Date _____
 Checked _____ Date _____
 Approved _____ Date _____



STANDARD DWG. NO.

IUM-620B(W)

SHEET 1 OF 1

DATE 3-16-2012

EROSION CONTROL BLANKET:

STANDARD	DESCRIPTION
IUM-530	EROSION CONTROL BLANKET
IUM-531	EROSION CONTROL BLANKET, TURF REINF. MAT

INLET PROTECTION:

STANDARD	DESCRIPTION
IL-555	EXCAVATED DRAIN
IL-560	FABRIC DROP
IL-562	SOD FILTER
IUM-561C	FILTER BAG
IUM-561D	SEDIMENT BAG/FILTER

END SECTION INLET PROTECTION:

STANDARD	DESCRIPTION
IL-508SF	CULVERT INLET PROTECTION - SILT FENCE
IL-508ST	CULVERT INLET PROTECTION - STONE

DITCH CHECK:

STANDARD	DESCRIPTION
IUM-514PC	PLASTIC PERMEABLE
IUM-514RC	ROLLED EROSION CONTROL
IUM-514SC	SYNTHETIC POROUS CONTROL
IUM-514UF	URETHANE FOAM GEOTEXTILES
IUM-514VC	VEGETATED EROSION CONTROL
IL-605CA	ROCK CHECK DAM - COARSE AGGREGATE
IL-605R	ROCK CHECK DAM - RIPRAP

SILT FENCE:


STANDARD	DESCRIPTION
IUM-620A	SILT FENCE
IUM-620AW	SILT FENCE WITH WIRE SUPPORT
IUM-620BW	SILT FENCE SPLICING

NOTE:

STANDARDS ARE PER THE NATURAL RESOURCES CONSERVATION SERVICE AS PUBLISHED IN THE ILLINOIS URBAN MANUAL, LATEST EDITION.

EROSION CONTROL

DATE: 4-3-13




HYDRANT SPECIFICATIONS:

MUELLER SUPER CENTURION 200, WATEROUS PACER MODEL WB-67-250, OR CLOW MEDALLION.
 MECHANICAL JOINT SHOE WITH 6" RESILIENT WEDGE AUXILIARY VALVE.
 5-1/4" VALVE OPENING
 5' MIN. COVER OVER HYDRANT LATERAL
 "HYDRAFINDER" STANDARD HYDRANT LOCATOR, INSTALLED
 VALVE BOX SHALL HAVE A VALVE BOX STABILIZER INSTALLED*
 *VALVE BOX ADAPTOR #2 TYPE A, AS MADE BY ADAPTOR, INC. OR APPROVED EQUAL.

NOT TO SCALE


**HYDRANT
INSTALLATION**

DATE: 11-19-09



LEGEND

- ① SUB-BASE GRANULAR MATERIAL
- ② EXISTING PAVEMENT
- ③ EXISTING STRUCTURE
- ④ FRAME AND LID (SEE NOTES)
- ⑤ CLASS S1 CONCRETE
- ⑥ PROPOSED HMA SURFACE COURSE
- ⑦ PROPOSED HMA BINDER COURSE
- ⑧ PROPOSED MORTAR, STEEL SHIMS & ADJUSTING RINGS 8" MAXIMUM
- ⑨ FULL DEPTH SAW CUT



NOTES:

EXISTING FRAMES AND LIDS SHALL BE REMOVED AND RETURNED TO THE CITY OF ST. CHARLES BY THE CONTRACTOR AND SHALL BE REPLACED AS DIRECTED BY THE ENGINEER.

CITY OF ST. CHARLES CASTINGS ARE THE PROPERTY OF THE CITY AND THE CONTRACTOR SHALL NOTIFY THE CITY OF REMOVAL AND DISPOSITION OF THE CASTINGS.

INSTALLATION OF NEW OR ADJUSTMENTS TO EXISTING FRAMES & LIDS WILL NOT BE PAID FOR SEPARATELY BUT ARE INCLUDED AS PART OF THE COST PER EACH ARE INCLUDED AS PART OF THE COST PER EACH ADJUSTED, SPECIAL".

CONSTRUCTION PROCEDURES

STAGE 1 (AFTER PAVEMENT MILLING AND PLACEMENT OF HMA BINDER)


- A) FULL DEPTH SAW CUT 5' X 5' SQUARE OR DIAMOND AROUND CENTER OF FRAME TO BE ADJUSTED
- B) REMOVE FRAME, EXISTING PAVEMENT AND AGGREGATE MATERIAL TO A DEPTH OF 2" BELOW TOP OF MANHOLE STRUCTURE OR 2" BELOW BOTTOM OF LOWEST ADJUSTMENT RING.
- C) ADJUST NEW FRAME TO MATCH PROPOSED HMA PAVEMENT SURFACE GRADE USING MORTAR, STEEL SHIMS EMBEDDED IN MORTAR, AND PRECAST CONCRETE ADJUSTING RINGS.
- D) COMPACT EXISTING AGGREGATE STONE BASE.
- E) FILL 5'X5' SURROUNDING SPACE WITH IDOT APPROVED CLASS S1 CONCRETE TO THE SAME ELEVATION OF THE TOP OF THE BINDER COURSE.
- F) PAVE SURFACE COURSE OVER 5' X 5' CONCRETE COLLAR.

THE PROCEDURE EXPLAINED ABOVE SHALL CONFORM TO THE APPLICABLE PORTIONS OF SECTIONS 353, 406, 602, AND 603 OF THE STANDARD SPECIFICATIONS

NOT TO SCALE

FRAME
AND LID
ADJUSTMENT
WITH
CONCRETE
COLLAR

DATE: 12-8-10



NOTE:

1. INLET TO BE CONSTRUCTED OF PRECAST REINFORCED CONCRETE.
2. INLET MUST CONFORM TO ASTM C-478.
3. NON-PRECAST OPENINGS SHALL BE CORED AND RUBBER BOOTED.
4. MAXIMUM DEPTH FROM INVERT OF OUTLET PIPE TO TOP OF FRAME SHALL NOT EXCEED 42 INCHES. IF DESIGN OR CONSTRUCTION REQUIRES DEPTH BEYOND 42 INCHES, STRUCTURE SHALL BE REVISED TO A 48 INCH DIAMETER TY A MANHOLE.



NOT TO SCALE

TYPE A INLET
DETAIL

DATE: 3-31-09

SPECIAL LETTERED R-1713 HDSI WATER VAULT, SANITARY AND STORM SEWER MANHOLE COVER

1 1/2" (38.1 mm) LETTERS
(RECESSED FLUSH)




HEAVY DUTY
MATERIAL ASTM A48 CL 35
MACHINED BEARING SURFACE
COVER WT: 125 LBS (56.7 kg)

NOT TO SCALE

STANDARD
COVER
DETAIL

DATE: 11-19-09

MOUNTABLE CONCRETE CURB & GUTTER




NOTES:

- 1.) 1/2" THICK PREFORMED EXPANSION JOINTS SHALL BE INSTALLED AT 50 FOOT INTERVALS. PROVIDE 2-3/4" STEEL DOWEL BARS AT EXPANSION JOINTS.
- 2.) EXPANSION JOINTS SHALL BE INSTALLED ON EACH SIDE, A DISTANCE OF 2 FEET FROM A STRUCTURE THAT FALLS WITHIN THE CURB AND GUTTER.
- 3.) CONSTRUCTION JOINTS SHALL BE SAWED TO A MINIMUM DEPTH OF 2 INCHES AND PLACED AT 10 FOOT INTERVALS. SAW CUTS SHALL BE SAWED NO SOONER THAN 6 HOURS AND NO LATER THAN 24 HOURS AFTER PLACEMENT OF CONCRETE.
- 4.) CURBS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" (IDOT). MOST RECENT EDITION UNLESS NOTED OR DEPICTED HEREIN.
- 5.) A PROTECTIVE COAT SHALL BE APPLIED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

MOUNTABLE
CURB & GUTTER

DATE: 9-30-10



FOR DESIGN OF RECTANGULAR WEIR:

USE $Q=CLH^{3/2}$

WHERE Q= RELEASE RATE

C= 3.0 FOR BROAD-CRESTED RECTANGULAR WEIRS

L= WEIR OPENING

T= WALL THICKNESS (6" MIN)

H= HEAD (6" MIN)

USE COMPARABLE RELATIONSHIPS FOR DESIGN OF OVERFLOW STRUCTURES.

NOTES:


1. STRUCTURE TO BE CONSTRUCTED OF REINFORCED CONCRETE, IDOT CLASS SI (6.1 BAG MIX) MIN 3500 PSI AT 14 DAYS, WITH 5% TO 7% AIR ENTRAINMENT. (NO FLY ASH ALLOWED)
2. SMOOTH FINISH -1" CHAMFER ON ALL EXPOSED EDGES
3. PROVIDE MIN #4 REBARS IN FOOTING AND WEIR, 12" O.C., E.W.
4. BACKFILL MATERIAL TO BE INORGANIC COHESIVE SOIL, COMPACTED IN MAXIMUM 12" (LOOSE) LIFTS TO AT LEAST 90% MODIFIED PROCTOR DENSITY (ASTM D-1557)
5. EROSION CONTROL MATERIAL TO BE PROVIDED IN FRONT AND REAR OF WEIR OPENING.

NOT TO SCALE


OVERFLOW
(WEIR)
STRUCTURE
DETAIL

DATE: 3-31-09


A. FLEXIBLE PAVEMENT



B. RIGID PAVEMENT



C. COMPOSITE PAVEMENT



NOTE:

SECTIONS REPRESENT THE MINIMUM CROSS SECTION ALLOWED.


1. HOT MIX ASPHALT SURFACE & BINDER COURSE SHALL CONFORM TO IDOT HMA MIX SELECTION TABLE.
2. PORTLAND CEMENT CONCRETE SHALL CONFORM TO IDOT CLASS PV, MIN. 3500 PSI (6.1 BAG MIX) AT 14 DAYS. WITH 5% TO 8% AIR ENTRAINMENT. (NO FLY ASH ALLOWED)
3. ALL SUBGRADE SHALL HAVE A MINIMUM ILLINOIS BEARING RATIO (IBR) OF 3.0, AND BE COMPACTED TO AT LEAST 90% MODIFIED PROCTOR DENSITY (ASTM D-1557)

NOT TO SCALE


MINIMUM
PAVEMENT
DETAILS

DATE: 2-3-10


A. FLEXIBLE PAVEMENT



B. RIGID PAVEMENT



C. COMPOSITE PAVEMENT



NOTE :

1. ALL PAVEMENT PATCHES SHALL BE SAWCUT FULL-DEPTH A MINIMUM OF ONE FOOT BEYOND THE LIMITS OF THE FAILED PAVEMENT IN ALL DIRECTIONS.
2. PORTLAND CEMENT CONCRETE SHALL CONFORM TO IDOT CLASS PP MIN. 3.500 PSI (6.1 BAG MIX) AT 14 DAYS, WITH 5 % TO 7 % AIR ENTRAINMENT. (NO FLY ASH ALLOWED)

DATE: 12-8-10


NOT TO SCALE
PAVEMENT
PATCH
DETAIL

NON-SHEAR BAND SEAL
COUPLING OR EQUAL

BUTT PIPES OF MATCHING
DIAMETERS TOGETHER

EXISTING OR
REPLACED SEWER

EXISTING SEWER




NOT TO SCALE


PIPE
COUPLING
DETAIL

DATE: 3-31-09

4" PIPE UNDERDRAIN PLAN



SECTION A-A



NOT TO SCALE



PIPE
UNDERDRAIN
DETAIL

NOTE:

UNDERDRAIN TO BE INSTALLED BELOW ALL NEW ROADWAYS

DATE: 1-20-11

PLANTING GUIDELINES



VEGETATION HEIGHT LIMITS ARE FOR MATURE PLANTS


VEGETATION RESTRICTION NOTES:

1. AREA AROUND THE HYDRANT 5 FEET IN RADIUS SHALL REMAIN FREE OF ALL VEGETATION EXCEPT FOR GRASS.
2. AREA AROUND THE HYDRANT FROM 5 FEET TO 10 FEET MAY HAVE VEGETATION WITH A 24" TO 30" HEIGHT EXCEPT FOR THAT PORTION OF THE AREA IN FRONT OF THE HYDRANT CREATING A 60 ° ARC.

NOT TO SCALE

PLANTING
GUIDLINES

DATE: 3-31-09




NOTES:

1. THE ONE FOOT BUFFER STRIP ALONG SIDEWALKS IS ONLY REQUIRED IF A SIDEWALK IS PRESENT.
2. PLANTS ALONG STREETS, CURBS AND SIDEWALKS SHALL BE OF A VARIETY THAT REACHES A MAXIMUM HEIGHT OF 8 INCHES.
3. PLANTING HEIGHTS SHALL BE CONSISTENT WITH THE LIMITS SHOWN ABOVE.
4. ALL PLANTS SHALL BE OF A VARIETY THAT DOES NOT HANG OVER ONTO THE STREET, CURB OR SIDEWALK.

STANDARD PLANTING
PARKWAY DETAIL

DATE: 9-12-12

23" MAX.
SURFACE TO
FLARE OF CONE




NOTES:

1. 60" (MIN) INSIDE DIA. FOR ALL PRESSURE CONNECTION VAULTS.
2. ALL NON-PRECAST PIPE OPENINGS TO BE CORED AND RUBBER BOOTED.
3. BACKFILL MATERIAL SHALL BE IDOT CA-7 VIRGIN CRUSHED LIMESTONE.
4. a) MECHANICAL JOINT BOLTS & NUTS SHALL BE COMPOSED OF CORE-TEN.
b) ALL OTHER HEXAGONAL BOLTS, NUTS & WASHERS SHALL BE COMPOSED OF 304 GRADE STAINLESS STEEL.
5. USE ECCENTRIC CONE ONLY.
6. VALVE VAULT MUST CONFORM TO ASTM C-478.
7. ALL SECTIONS TO BE TONGUE AND GROOVED.
8. BLOCKING SHALL NOT INTERFERE WITH BOLT MAINTENANCE OR REPLACEMENT.
9. PRIOR TO THE PLACEMENT OF FINAL LAYER OF ROADWAY, FRAMES AND ADJUSTING RINGS LOCATED WITHIN PAVED AREAS SHALL BE SET IN AN IDOT APPROVED CONCRETE "SI" MIXTURE.

NOT TO SCALE

**PRESSURE
CONNECTION
DETAIL**

DATE: 7-27-10




NOTES:

1. TRENCH BACKFILL MATERIAL SHALL CONSIST OF CA-7 (VIRGIN CRUSHED LIMESTONE) UNDER PAVED AREAS OR WITHIN ZONE OF INFLUENCE, OR FA-6 (CLEAN BROWN BEACH SAND) IN NON-PAVED AREAS.
2. ALL MATERIALS SHALL BE PROPERLY COMPACTED PER SPECIFICATIONS (INUNDATION OR WATER JETTING NOT ALLOWED)
3. ALL TRENCH EXCAVATIONS SHALL MEET OSHA REQUIREMENTS.
4. ALL STORM SEWER SMALLER THAN 15" DIA. THAT WILL BE PUBLICLY OWNED & MAINTAINED SHALL BE RIGID PVC PIPE, MINIMUM SDR 26 WITH PUSH-ON GASKET JOINTS.

NOT TO SCALE

PVC PIPE
TRENCH
DETAIL

DATE: 3-26-13



NOTES:

1. TRENCH BACKFILL MATERIAL SHALL CONSIST OF CA-7 (VIRGIN CRUSHED LIMESTONE) UNDER PAVED AREAS OR WITHIN ZONE OF INFLUENCE, OR FA-6 (CLEAN BROWN BEACH SAND) IN NON-PAVED AREAS.
2. ALL MATERIALS SHALL BE PROPERLY COMPACTED PER SPECIFICATIONS (INUNDATION OR WATER JETTING NOT ALLOWED)
3. ALL TRENCH EXCAVATIONS SHALL MEET OSHA REQUIREMENTS.
4. ALL STORM SEWER SMALLER THAN 15" DIA. THAT WILL BE PUBLICLY OWNED & MAINTAINED SHALL BE RIGID PVC PIPE, MINIMUM SDR 26 WITH PUSH-ON GASKET JOINTS.


NOT TO SCALE

RCP & DIP
TRENCH
DETAIL

DATE: 3-26-13

RESTRICTOR STRUCTURE

96" MIN. DIA PRECAST
CONCRETE CATCH BASIN
WITH 6" THICK REINFORCED
CONCRETE BAFFLE WALL




NOTES:

1. RESTRICTOR SIZE TO BE APPROVED BY THE CITY ENGINEER.
2. MANHOLES MUST CONFORM TO ASTM C-478.
3. MANHOLE SECTIONS TO BE TONGUE AND GROOVED.
4. NON-PRECAST OPENINGS SHALL BE CORED AND RUBBER BOOTED.
5. MORTAR ALL PIPE PENETRATIONS INSIDE AND OUTSIDE OF STRUCTURE.
6. IN "SUBMERGED" CONDITIONS, ALL PIPE PENETRATIONS TO BE CORED, RUBBER BOOTED AND INTERIOR MORTARED.

NOT TO SCALE

RESTRICTOR STRUCTURE

DATE: 10-25-11




NOTES:

1. FOR PROPOSED STORM SEWER SERVICE $\leq 6"$ ON RCP PIPE $\geq 15"$, CORE THE PIPE AND USE A BOOT CONNECTION.
2. FOR PROPOSED STORM SEWER SERVICE $\geq 8"$, A MANHOLE SHALL BE INSTALLED.
3. FOR CONNECTING SANITARY OR STORM SEWER SERVICE TO AN EXISTING SANITARY OR STORM SEWER $\leq 12"$, REMOVE A SECTION OF PIPE AND INSTALL A TEE OR WYE CONNECTION.
4. FOR CONNECTING SANITARY SEWER SERVICE TO AN EXISTING SANITARY SEWER $\geq 15"$, CIRCULAR SAW-CUT AND USE A HUB WYE OR TEE SADDLE CONNECTION.
5. FOR PROPOSED STORM OR SANITARY SEWER SERVICES, ENCASE ALL CONNECTIONS IN LOW STRENGTH CONCRETE TO PREVENT THE FITTINGS FROM ROTATING.
6. FOR TRENCHES WITHIN AN EXISTING PAVED SURFACE AREA, CA-7 (VIRGIN CRUSHED LIMESTONE) BACKFILL SHALL BE USED.
7. FOR PROPOSED 6" STORM SEWER SUMP LINE, INSTALL PLUG AND 2" X 4" POST AT END OF LINE.

NOT TO SCALE

SANITARY
 AND STORM
 SERVICE
 DETAIL

DATE: 12-8-10




NOTES:

1. MANHOLES MUST CONFORM TO ASTM C-478.
2. MANHOLE SECTIONS TO BE TONGUE AND GROOVED.
3. BENCHES MUST BE PROVIDED IN ALL SANITARY SEWER MANHOLES
4. USE EXTERNAL LIFTING "HOLES" ONLY, BUT NOT FULL PENETRATION.
5. NON-PRECAST OPENINGS SHALL BE CORED AND RUBBER BOOTED.
6. PIPE PENETRATIONS TO BE RUBBER BOOTED AND INTERIOR MORTARED.
7. USE ECCENTRIC CONE ONLY.
8. PRIOR TO THE PLACEMENT OF FINAL LAYER OF ROADWAY, FRAMES AND ADJUSTING RINGS LOCATED WITHIN PAVED AREAS SHALL BE SET IN AN IDOT APPROVED CONCRETE "SI" MIXTURE.

NOT TO SCALE

SANITARY
MANHOLE
DETAIL

DATE: 7-27-10



NOTES:


1. CORE-DRILL CIRCULAR OPENING IN MANHOLE WALL OF DIAMETER TO FIT THE REQUIRED BOOT SIZE.
2. KOR-N SEAL FLEXIBLE RUBBER BOOT (MANUFACTURED BY NATIONAL POLLUTION CONTROL SYSTEMS, INC. OR AS APPROVED BY THE ENGINEERING DEPARTMENT) SHALL BE USED FOR WATERTIGHT CONNECTION.
3. CUT, SHAPE AND SLOPE NEW INVERT CHANNEL IN THE EXISTING CONCRETE BENCH FOR SMOOTH FLOW FROM NEW SANITARY SEWER CONNECTION.
4. CLEAN EXISTING MANHOLE OF ANY DIRT, CONCRETE OR DEBRIS WHICH MAY ACCUMULATE DURING THE CONSTRUCTION PROCESS.

NOT TO SCALE

SANITARY SEWER
CONNECTION
TO EXISTING
MANHOLE

DATE: 3-31-09

SERVICE BOX IN PAVED AREA




NOT TO SCALE


SERVICE BOX
IN
PAVED AREA

DATE: 3-31-09

DEPRESSED CURB



CURB & GUTTER




NOTES:

1. SEE TYPICAL DETAIL FOR CURB AND GUTTER FOR CURB DIMENSIONS AND SPECIFICATIONS.

NOT TO SCALE

SIDEWALK AT CURB AND GUTTER

DATE: 3-31-09




NOTES:

1. MANHOLES MUST CONFORM TO ASTM C-478.
2. MANHOLE SECTIONS TO BE TONGUE AND GROOVED.
3. BENCHES MUST BE PROVIDED IN ALL STORM SEWER MANHOLES.
4. NON-PRECAST OPENINGS SHALL BE CORED AND RUBBER BOOTED.
5. MORTAR ALL PIPE PENETRATIONS INSIDE AND OUTSIDE OF STRUCTURE.
6. IN "SUBMERGED" CONDITIONS, ALL PIPE PENETRATIONS TO BE CORED, RUBBER BOOTED AND INTERIOR MORTARED.
7. PRIOR TO THE PLACEMENT OF FINAL LAYER OF ROADWAY, FRAMES AND ADJUSTING RINGS LOCATED WITHIN PAVED AREAS SHALL BE SET IN AN IDOT APPROVED CONCRETE "SI" MIXTURE.

DATE: 7-27-10

NOT TO SCALE

TYPE
A & B
STORM
MANHOLE
DETAIL




NOTES:

1. RESTRICTOR SIZE TO BE APPROVED BY THE CITY ENGINEER. MINIMUM RESTRICTOR DIAMETER IS 3".
2. MANHOLES MUST CONFORM TO ASTM C-478.
3. MANHOLE SECTIONS TO BE TONGUE AND GROOVED.
4. BENCHES MUST BE PROVIDED IN ALL STORM SEWER MANHOLES.
5. NON-PRECAST OPENINGS SHALL BE CORED AND RUBBER BOOTED.
6. MORTAR ALL PIPE PENETRATIONS INSIDE AND OUTSIDE OF STRUCTURE.
7. IN "SUBMERGED" CONDITIONS, ALL PIPE PENETRATIONS TO BE CORED, RUBBER BOOTED AND INTERIOR MORTARED.
8. PRIOR TO THE PLACEMENT OF FINAL LAYER OF ROADWAY, FRAMES AND ADJUSTING RINGS LOCATED WITHIN PAVED AREAS SHALL BE SET IN AN IDOT APPROVED CONCRETE "SI" MIXTURE.

DATE: 7-27-10

NOT TO SCALE

TYPE
A & B
STORM
MANHOLE
WITH
RESTRICTOR



NOTE:


THE CITY OF ST. CHARLES ALLOWS RESIDENTS TO CONNECT SUMP PUMP DISCHARGE LINES TO THE PUBLIC STORM SEWER SYSTEM. SUMP PUMPS SHALL BE DESIGNED WITH A MINIMUM 2" AIR GAP. A RIGID FOUR-INCH (4") DIAMETER PVC PIPE CAN BE USED TO CONNECT THE INDIVIDUAL SUMP PUMP SERVICE TO THE STORM SEWER. IN NO EVENT SHALL THE SUMP PUMP DISCHARGE INTO THE SANITARY SEWER SYSTEM.

A PLUMBING PERMIT IS REQUIRED PRIOR TO ANY CONNECTION. INCLUDE A PLAT OF SURVEY WITH THE PERMIT APPLICATION, SHOWING THE POINT OF DISCHARGE AND CONNECTION TO THE STORM SEWER. THE SITE PLAN SHALL ALSO INCLUDE PIPE SPECIFICATIONS AND INVERT ELEVATIONS. CALL THE CITY ENGINEERING DIVISION 24 HOURS IN ADVANCE TO SCHEDULE AN INSPECTION.

NOT TO SCALE

**SUMP PUMP DISCHARGE
CONNECTION DETAIL**

DATE: 3-31-09




NOTE:

1. ALL BENDS OF 10° AND LARGER SHALL BE BLOCKED WITH AT LEAST 10" THICK PREFORMED CONCRETE BLOCK(S) AGAINST UNDISTURBED VERTICAL EARTH FACE.
2. ALL CONCRETE TO BE MIN. 3,000 PSI.
3. IN ADDITION TO THE ABOVE THRUST BLOCKING: ALL MECHANICAL JOINTS, BENDS OVER 10° AND FIRE HYDRANTS SHALL HAVE A "MEGALUG" RESTRAINT, OR AS APPROVED BY THE ENGINEERING DIVISION. BOLTS SHALL BE "COR-TEN".

DATE: 3-2-11

NOT TO SCALE

THRUST BLOCK
INSTALLATION
DETAILS



NOTES:


1. AN ON-SITE DRAINAGE SWALE SHALL BE LOCATED BETWEEN THE TOPSOIL STOCKPILE AND OFF-SITE PROPERTY.
2. REFERENCE IS MADE TO THE SILT FENCE DETAIL FOR MATERIALS AND INSTALLATION METHODS.
3. IF THE STOCKPILE IS TO REMAIN FOR MORE THAN 14 DAYS, IT SHALL BE STABILIZED WITH BURLAP MATTING OR SEEDED WITHIN 7 DAYS OF COMPLETION TO MINIMIZE EROSION.
4. INSPECTION OF SILT FENCES SHALL BE AT LEAST ONCE PER WEEK AND AFTER RAIN EVENTS IN EXCESS OF 1/2". REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED.
5. SEDIMENT TRAPPED BY THE FENCES SHALL BE REMOVED AND PROPERLY DISPOSED OF WHENEVER SIGNIFICANT ACCUMULATION OCCURS.
6. SILT FENCES SHALL BE MAINTAINED IN PLACE UNTIL TOPSOIL STOCKPILE HAS BEEN ELIMINATED AND SHALL BE REMOVED ONLY WHEN DIRECTED BY THE CITY.

NOT TO SCALE

TEMPORARY
TOPSOIL
STOCKPILE
DETAIL

DATE: 3-31-09

SECTION A-A




NOTES:

1. 48" MIN. INSIDE DIA. FOR VALVES LESS THAN 8" DIA.
60" MIN. INSIDE DIA. FOR ALL OTHER VALVE VAULTS.
2. VALVE VAULT MUST CONFORM TO ASTM C-478.
3. USE ECCENTRIC CONE ONLY.
4. VAULT SECTIONS TO BE TONGUE AND GROOVED.
5. NON-PRECAST PIPE OPENINGS TO BE CORED AND RUBBER BOOTS INSTALLED.
6. BACKFILL MATERIAL SHALL BE IDOT CA-7 VIRGIN CRUSHED LIMESTONE.
7. a) MECHANICAL JOINT BOLTS, NUTS & WASHERS SHALL BE COMPOSED OF CORE-TEN.
b) ALL OTHER HEXAGONAL BOLTS, NUTS & WASHERS SHALL BE COMPOSED OF 304 GRADE STAINLESS STEEL.
8. PRIOR TO THE PLACEMENT OF FINAL LAYER OF ROADWAY, FRAMES AND ADJUSTING RINGS LOCATED WITHIN PAVED AREAS SHALL BE SET IN AN IDOT APPROVED CONCRETE "SI" MIXTURE.

DATE: 7-27-10

NOT TO SCALE

VALVE
VAULT
DETAIL



NOTES:

1. HORIZONTAL AND VERTICAL SEPARATION BETWEEN WATERMAINS AND SEWERS SHALL COMPLY WITH APPLICABLE SECTIONS OF THE CITY OF ST. CHARLES ENGINEERING GUIDE OR IEPA REQUIREMENTS, WHICHEVER IS MORE STRINGENT.
2. CONTRACTOR MAY BEND WATER MAIN PIPE UNIFORMLY UNDER SEWERS WITHOUT USING FITTINGS, PROVIDED THAT JOINT DEFLECTION DOES NOT EXCEED 5 DEGREES PER JOINT FOR PIPE UNDER 14" IN DIAMETER AND 3 DEGREES PER JOINT FOR PIPE 14" AND OVER IN DIAMETER. IF FITTINGS ARE USED, CONTINUOUS STRAPPING WITH RODS, STRAPS, NUTS AND BOLTS BELOW NORMAL WATERMAIN DEPTH ARE REQUIRED, OR RETAINER GLANDS MAY BE USED IN LIEU OF STRAPPING. RETAINER GLANDS TO BE CLOW No. F-1058 OR APPROVED EQUAL.
3. ALL SANITARY SEWER (INCLUDING SERVICE) CROSSINGS WHERE THE WATER MAINS OR WATER SERVICES ARE LESS THAN 18" VERTICALLY ABOVE THE SEWER SHALL BE POLYVINYL CHLORIDE PRESSURE PIPE (SDR 26-160 PSI) AND SHALL CONFORM WITH THE LATEST REVISION OF ASTM D- 2241. JOINTS SHALL CONFORM TO ASTM D-3139 AND ELASTOMERIC GASKETS SHALL CONFORM TO ASTM F-477. THE SAME PIPE AND JOINT MATERIALS SHALL BE USED WHENEVER WATER MAIN CROSSES BELOW THE SEWER.
4. ALL STORM SEWER (INCLUDING SERVICE) CROSSINGS WHERE THE WATER MAINS ARE LESS THAN 18" VERTICALLY ABOVE THE SEWER SHALL BE REINFORCED CONCRETE PIPE, ASTM C-361, CLASS D-25, WITH BELL AND SPIGOT JOINTS AND RUBBER GASKETS, OR PVC SDR 26 AS SPECIFIED IN NOTE 3 ABOVE. THE SAME PIPE AND JOINT MATERIAL SHALL BE USED WHENEVER WATER MAIN CROSSES BELOW THE SEWER.
5. FOR NEW SEWER INSTALLATIONS CROSSING OVER WATER MAINS, THE ENTIRE RUN OF NEW SEWER SHALL BE WATER MAIN QUALITY PIPE, EXTENDING FROM STRUCTURE TO STRUCTURE ON EACH SIDE OF THE CROSSING.

NOT TO SCALE

**WATER MAIN
CROSSING
DETAIL**

DATE: 3-31-09

Minimum Restrained Lengths (in feet) back from both sides of fitting

Fitting type/nominal size	4"	6"	8"	10"	12"	16"	
90 Degree Bend	17	25	32	38	45	59	
45 Degree Bend	7	10	13	16	19	24	
22.5 Degree Bend	3	5	6	8	9	12	
11.25 Degree Bend	2	2	3	4	4	6	
Dead End	39	55	73	87	103	134	
Top Side Vertical Offset * (45 Degree)	16	23	30	36	43	55	
Bottom Side Vertical Offset * (45 Degree)	4	6	8	10	11	15	
Tee Run X Branch **							
6" by	1	17					
8" by	1	5	34				
10" by	1	1	24	49			
12" by	1	1	15	41	65		
16" by	1	1	1	26	52	95	
Reducer ***							
6" by	28						
8" by	52	30					
10" by	71	54	29				
12" by	90	75	55	51			
16" by	123	113	97	94	54		

* Vertical offset with minimum 10' of solid pipe between upper and lower bend.




** Tee with MINIMUM 10' solid pipe on both sides of run.

Number indicates length of branch to be restrained.

*** Length back from Large Eng of Reducer.

WATER MAIN
RESTRAINT

DATE: 3-31-09



A. CURB BOX:

1. MUELLER H-10300 WITH 1-1/4" I.D. UPPER SECTION AND 2" MINEAPOLIS TAPPED BASE.
2. A.Y. McDONALD 5615 1-1/4"

B. CURB STOP:

- MUELLER B-25155 (1", 1 1/2", 2")
 FORD B-44-444-Q 1"
 B-44-666-Q 1 1/2"
 B-44-777-Q 2"
 A.Y. McDONALD 6104-Q 1", 1 1/2", 2"
 Q SERIES BRASS

C. CORPORATION STOP:

- MUELLER B-25008,
 FORD FB1000 -4-Q 1"
 FB 1000-6-Q 1-1/2"
 FB 1000-7-Q 2"
 A.Y. McDONALD 4701-BQ 1", 1-1/2", 2"
 Q SERIES BRASS, WITH 90 SWIVEL ELBOW

NOTES:

1. PIPE SIZE CAN VARY, BUT 1" MINIMUM. OTHER APPURTENANCES SHALL REFLECT SAME.
2. COPPER PIPE SHALL BE ONE PIECE BETWEEN TAP AND CURB BOX.
3. PLACE BETWEEN SIDEWALK AND PROPERTY LINE. KEEP BOXES OUT OF SIDEWALKS AND DRIVEWAY.
4. MINIMUM OF 3' BETWEEN TAPS AND 3' TO NEAREST JOINT.
5. 1" SERVICE MAY BE DIRECTLY TAPPED INTO 6" OR LARGER MAIN. LARGER SERVICES REQUIRE A SMITH-BLAIR 372 OR APPROVED EQUAL STAINLESS STEEL TAP THROUGH SLEEVE.

NOT TO SCALE

COPPER
 WATER SERVICE
 CONNECTION
 DETAILS

DATE: 11-2-09