


INSTALL 2 CONTINUOUS BARS  
 TIED TO EXISTING CURB AND GUTTER  
 #4 BARS IN RESIDENTIAL  
 #6 BARS IN INDUSTRIAL/COMMERCIAL

**NOTES:**

1. CONTRACTION JOINTS SHALL BE PLACED AT 15' INTERVALS, AND SHALL BE FORMED BY SAW CUTTING TO A DEPTH OF AT LEAST TWO INCHES.
2. EXPANSION JOINTS SHALL BE PLACED AT 60' (MAX) INTERVALS, AT ALL POINTS OF CURVATURE, AND AT THE END OF EACH POUR.



**CITY OF ST. CHARLES**  
 ILLINOIS • SINCE 1834  
*Pride of the Fox*

**MOUNTABLE  
 CONCRETE CURB & GUTTER**

DATE: 9-10-2021

NOT TO SCALE

REVISED:

DRAWING NO. E-05