


**NOTES:**

1. PLACEMENT OF PAVER BRICKS OR STAMPED CONCRETE FOR DRIVEWAY APRONS REQUIRE A NON-STANDARD PAVEMENT, NOTORIZED PERMIT AGREEMENT AND A "COVENANT RUNNING WITH THE LAND" DOCUMENT, WHICH MUST BE RECORDED AT KANE COUNTY RECORDER'S OFFICE PRIOR TO CONSTRUCTION.
2. THE SAND FOR THE BEDDING LAYER SHALL BE DELIVERED TO THE SITE A MINIMUM OF 24 HOURS PRIOR TO PLACEMENT TO ALLOW FOR THE MOISTURE TO DRAIN FROM THE MATERIAL.
3. THE SAND BED SHALL BE COMPACTED PRIOR TO PLACEMENT OF THE PAVER BRICKS. DISTURBED AREAS OR SCREEDED AREAS LEFT OVERNIGHT SHALL BE REMOVED AND RESCREEDED. FOLLOWING THE PLACEMENT OF THE PAVER BRICKS, FA-1 SAND SHALL BE SPREAD ACROSS THE SURFACE OF THE PAVERS AND COMPACTED WITH A VIBRATORY PLATE COMPACTOR.
4. THE BASE COURSE SHALL BE CONSTRUCTED OF CA-6 MATERIAL COMPACTED IN TWO LIFTS.
5. EDGE RESTRAINT SHALL BE PROVIDED ON ALL SIDES OF THE PAVER CONSTRUCTION IN THE FORM OF STANDARD CURB AND GUTTER, SIDEWALK, OR A TYPICAL EDGE RESTRAINT.
6. UNDERCUTS AND THE CONSTRUCTION OF A SUBBASE SHALL OCCUR AS NECESSARY.



**CITY OF ST. CHARLES**  
 ILLINOIS • SINCE 1834  
*Pride of the Fox*

**BRICK PAVER DRIVEWAY**

DATE: 5-12-2021

NOT TO SCALE

REVISED:

DRAWING NO. E-10